

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20304-00-00
Spot: SW Sec/Twnshp/Rge: 35-18S-5W
1240 feet from S Section Line, 3881 feet from E Section Line
Lease Name: LARSON ROBERT Well #: 1
County: MCPHERSON Total Vertical Depth: 1025 feet

Operator License No.: 32081
Op Name: SMOKEY VALLEY RESOURCES, INC.
Address: PO BOX 209
DEXTER, KS 67038

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	3.5	1025		75 SX
SURF	7	198		75 SX

35.00

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/05/2009 12:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 01/05/2009 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

RIG UP-TAG BOTTOM. PERFORATE @ 700' AND 400'. RUN 1.5" TUBING TO 925' AND PUMP 10 SXS CEMENT. PULL TUBING TO 700' AND PUMP 25 SK'S CEMENT, PULL TUBING TO 400' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. USED 140 SX'S TOTAL.

Perfs:

Top	Bot	Thru	Comments
896	919		WINFIELD

INVOICED

DATE 1-28-09
INV. NO. 2009061126

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 15 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. LOG TECH #5582. COPELAND TICKET #C-33225

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

PK