

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20165-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 3-3S-14E
3661 feet from S Section Line, 2497 feet from E Section Line
Lease Name: EPPLE A Well #: 2
County: NEMAHA Total Vertical Depth: 3828 feet

Operator License No.: 6101
Op Name: TEICHGRAEBER OIL, INC.
Address: 700 N MAIN ST
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3828		220 SX
SURF	8.625	260		153 SX

124.41

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/05/2008 8:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: RICK STOUT Company: TEICHGRAEBER OIL, INC. Phone: (620) 583-2173

Proposed Plugging Method: AS RECOMMENDED BY KCC, 20 SACKS @ BOTTOM ABOVE PERFORATIONS, TOP PLUG FROM 310 TO SURFACE.

Plugging Proposal Received By: STEVE KORF Witness Type: NONE
Date/Time Plugging Completed: 03/07/2008 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

HAD TUBING AT 3686' AND PUMPED 20 SACKS OF CEMENT. SHOT THE 5 1/2" CASING AT 2199.5' AND 1301' BUT COULD NOT RETRIEVE ANY CASING. PULLED THE TUBING UP TO 1300' AND PUMPED 20 SACKS OF CEMENT. PULLED THE TUBING UP TO 350' AND CIRCULATED 50 SACKS OF CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3802	3808		
3582	3584		

RECEIVED
KCC DISTRICT #3

DEC 31 2008 *TCH*

CHANUTE, KS

INVOICED
DATE 1-28-09
INV. NO. 2009061127

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 12 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)