

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20537-00-01
Spot: NWNESW Sec/Twnshp/Rge: 34-24S-8W
2031 feet from S Section Line, 3396 feet from E Section Line
Lease Name: TREMBLEY UNIT Well #: 6X
County: RENO Total Vertical Depth: 3716 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3715	2440	150 SX
SURF	8.625	215		200 SX <u>120.77</u>

Well Type: SWD EOR KCC PKT UIC Docket No: E26989.2 Date/Time to Plug: 12/11/2008 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JASON BRUNS Company: BEREXCO, INC. Phone: (316) 265-3311

Proposed
Plugging
Method:

AS PER KCC

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 12/12/2008 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

LOCKSET @ 3295. SANDED BACK TO 3285' PLACED 5 SX OF CEMENT ON TOP OF SAND, SHOT CASING OFF @ 2440' PULLED CASING TO 1250' SPOTTED 35 SX OF CEMENT & 50 LBS OF HULLS, PULLED CASING TO 700' SPOTTED 35 SX OF CEMENT & 50 LBS OF HULLS, PULLED CASING TO 265' CIRCULATED TO SURFACE WITH 120 SX OF CEMENT AND 50 LBS OF HULLS.

Perfs:

Top	Bot	Thru	Comments
3492	3498		
3346	3349		

INVOICED
DATE 1-27-09
INV. NO. 2009061093

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 13 2009

Remarks: QUALITY CEMENT CO. TICKET #2244 60-40-4% POS MIX

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

12-23-08 Dist

PH