

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-051-23, 320-00-00

SW, Sec. 31, T 11 S, R 16 W

330 feet from N/S section line

1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5562

Lease Name PLANTER "B" Well # 1

Operator: LIBERTY ENTERPRISES  
Name &

County ELLIS

Address 308 West Mill  
PLAINVILLE, KANS.  
67663

Well Total Depth 3736 feet 121.42

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 216

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor PIONEER DRILL CO License Number \_\_\_\_\_

Address 308 WEST MILL, PLAINVILLE, MS. 67663

Company to plug at: Hour: 2:00 PM Day: 1st Month: Feb Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO TOM FLIM

(company name) PIONEER DRILL CO (phone) 913-434-4686

were: 8 5/8" - 216 FT SP. CUL. #135 5th 60/40 Poz. 2% GEL. - 3% CA-CL. (ALLIED)

ORDER 180 5th 50/50 Pozmix - 4% GEL. - 3% CA-CL. AND 8 5/8" PLUG

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 3630 FT #20 5th CNT. -> 2nd PLUG @ 1260 FT #20 5th CNT.

3rd PLUG @ 780 FT #80 5th -> 4th PLUG @ 240 FT #40 5th CNT.

5th PLUG SOLID BRIDGE @ 40 FT #10 5th CNT. Signed Mason Schmidt

10 5th IN RAT HOLE (CIRCULATE)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 3:15 PM Day: 1st Month: FEB. Year: 1983

ACTUAL PLUGGING REPORT

Plugged as stated above.  
Cemented by Allied CNT.

Remarks:

RECEIVED  
STATE CORPORATION COMMISSION  
3-14-1983  
MAR 14 1983  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED  
MAR 28 1983

DATE \_\_\_\_\_  
INV. NO. 3771-W

Signed Mason Schmidt  
(TECHNICIAN) (BOIC)