

15-051-25152-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25152-00-00  
Spot: N2NWNE Sec/Twnshp/Rge: 16-11S-20W  
4950 feet from S Section Line, 2105 feet from E Section Line  
Lease/Unit Name: LYND Well Number: 1  
County: ELLIS Total Vertical Depth: 3679 feet

Operator License No.: 6194  
Op Name: E S P DEVELOPMENT, INC.  
Address: 17746 177TH BOULEVARD  
PARADISE, KS 67658

Conductor Pipe: Size feet: 8 1/2  
Surface Casing: Size 8.625 feet: 237  
Production: Size feet:  
Liner: Size feet:

8119.57

Well Type: DH UIC Docket No: Date/Time to Plug: 08/18/2002 2:00 PM  
Plug Co. License No.: 9431 Plug Co. Name: VONFELDT DRILLING, INC  
Proposal Rcvd. from: DOUG BUDIG Company: VONFELDT DRILLING, INC Phone: (785) 483-6446

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 08/18/2002 6:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3678' w/25 sxs.  
2nd. Plug at 1475' w/25 sxs.  
3rd. Plug at 725' w/100 sxs.  
4th. Plug at 300' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

RECEIVED  
8-22-2002  
AUG 22 2002


KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 8-22-02

WTU # 2003060344

8-21-2002  
AUG 21 2002