

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 35 Twp. 9S Rge. 23 W(E) (W)

Location as "NE/CNW/SW" or footage from lines SW NW NW

Lease Owner D. G. Hansen

Lease Name Rice Well No. 4

Office Address Logan, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 30 19 63

Application for plugging filed April 30 19 63

Application for plugging approved April 30 19 63


Plugging commenced April 30 19 63

Plugging completed April 30 19 63

Reason for abandonment of well or producing formation too low structurally

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3980 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	198'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 540'
SET PLUG. PUT IN 20 SACKS CEMENT. FILLED
W/HEAVY MUD TO 190'. SET PLUG. PUT IN
20 SACKS CEMENT. FILLED WITH HEAVY
MUD UP TO 40'. SET PLUG. FILLED TO
TOP WITH 1 SACK HULLS AND 10 SACKS
CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
5-10-63

MAY 10 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.

Address 107 Rule Bldg. Wichita 2, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Jay H. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay H. Galloway
107 Rule Bldg.
(Address)

SUBSCRIBED AND SWORN TO before me this 3 day of May, 19 63

My commission expires May 20, 1963
Vicky Jacobs
Vicky Jacobs Notary Public.



OPERATOR	D. G. Hansen	SEC.	35-9S-23W
WELL NAME	Rice #4	LOC.	SW NW NW
TOTAL DEPTH	3980'	COUNTY	Graham
COMM.	4/22/63	STATE	Kansas
COMP.	4/30/63	ELEVATION	2446' R.B.
RIG NO.	#1	PRODUCTION:	D & A
CASING:	Set 198' (10 jts.) 8-5/8" OD Surface Casing.		

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	1550	Shale	1/2°	- 500'
1550	1745	Sand	1/2°	- 1500'
1745	1930	Red Bed		
1930	2017	Red Bed & Shale	3/4°	- 2000'
2017	2060	Anhydrite		
2060	2470	Shale-Shells		
2470	2790	Shale-Lime	1/2°	- 2500'
2790	3720	Lime-Shale	1/2°	- 3000'
3720	3980	Lime		

DST #1
3748-3765'

RECEIVED
STATE CORPORATION COMMISSION

MAY 10 1963

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.
By G. F. Galloway
G. F. Galloway
THIS 3 day of May, 1963
Vicky Jacobs
Vicky Jacobs - Notary Public



SUBSCRIBED AND SWORN TO, BEFORE ME,
My commission expires:
May 20, 1963

