

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County. Sec. 35 Twp. 9 Rge. 23 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE NE NW

Lease Owner D. G. Hansen

Lease Name Rice Well No. 2

Office Address Logan, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 7 19 63

Application for plugging filed February 7 19 63

Application for plugging approved February 7 19 63

Plugging commenced February 7 19 63

Plugging completed February 7 19 63

Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3950 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	189.09'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

/

Filled hole with heavy mud to 540'.
Set plug. Put in 20 sacks cement.
Filled with heavy mud to 180'. Set
plug. Put in 1/2 sacks hulls and
20 sacks cement. Filled with heavy mud
up to 40'. Set plug. Filled to top with
1/2 sacks hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
2-14-63
FEB 14 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.
Address 107 Rule Building, Wichita 2, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
107 Rule Bldg.
(Address)

SUBSCRIBED AND SWORN to before me this 11 day of February, 19 63

My commission expires May 20, 1963

Vicky Jacobs
Notary Public.



W E L L L O G

OPERATOR D. G. Hansen SEC. 35-9-23
 WELL NAME Rice #2 LOC. SE NE NW
 TOTAL DEPTH 3950 COUNTY Graham
 COMM. 1/28/63 COMP. 2/7/63 STATE Kansas
 RIG NO. 1 ELEVATION 2424K.B.
 CASING: Set 189.09' (9 jts.) 8-5/8" OD Surface Casing. PRODUCTION: D & A

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	150	Shale-Sand		
150	189	Shale		
189	715	Shale-Sand	500' - 1/2°	
715	1540	Shale	1000' - 3/4°	
1540	1710	Sand	1500' - 1/2°	
1710	2002	Red Bed	2000' - 1/2°	
2002	2043	Anhydrite		
2043	2060	Shale-Shells		
2060	2470	Shale		
2470	2510	Shale-Shells	2500' - 3/4°	
2510	2585	Lime-Shale		
2585	2830	Shale-Lime		
2830	3645	Lime-Shale	3000' - 3/4°	
3645	3950	Lime	3500' - 3/4°	

DST #1 3866-83
 DST #2 3882-3902

RECEIVED
 STATE CORPORATION COMMISSION

FEB 14 1963

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)


The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
 G. F. Galloway

THIS 11 day of February, 1963.

Vicky Jacobs
 Vicky Jacobs - Notary Public



SUBSCRIBED AND SWORN TO, BEFORE ME,

My commission expires:
 May 20, 1963