

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County. Sec. 4 Twp. 9 Rge. 24 (E) W (W)

Location as "NE/CNW&SW%" or footage from lines C-NE-NE

Lease Owner Herman George Kaiser Oil Producers

Lease Name Keith E KCC Well No. B-2

Office Address Box 143 Ellinwood, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed _____ 19____

Application for plugging filed _____ 19____

Application for plugging approved _____ 19____

Plugging commenced May 25 1957

Plugging completed June 2 1957

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4065' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	190'	none
				5 1/2	4065'	3143'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug back with sand from 4000' to 3940' and mixed and dumped 4 sx. cement from 3940' to 3892'. Pull casing to 700' and circulate mud and pump in 40 sx. cement from 700' to 580'. Pull rest of pipe. Mud to 35' and set 5' rock bridge from 35' to 30' and mix and dump 10 sx. cement from 30' to base cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Co. Permit no. 2

Address Box 304 Great Bend, Ks.

STATE OF Kansas, COUNTY OF Barton, ss.


I, W. J. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. J. Hall

SUBSCRIBED AND SWORN TO before me this 26 day of June 1957

My commission expires _____

(Address) _____
Delmer L. Postier
Notary Public.



RECEIVED
STATE CORPORATION COMMISSION
7-13-57
JUL 13 1957

PLUGGING
FILE SEC A. T. 9 R. 24.10
BOOK PAGE 18 LINE 10

CONSERVATION DIVISION
Wichita, Kansas

15-065-02161-0006

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Herman Geo. Kaiser, Oil Producer

SEC. 4 T. 9 R. 24W
 LOC. 150' W & 50' N of
 C NE NE $\frac{3}{4}$

FARM Keith "E"

NO. 2

COUNTY Graham

TOTAL DEPTH 4065'


COMM. 4/24/57

COMP. 5/4/57

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED



CASING

20	10
15	8 190'
12	6
13	5 4064'

2457 K. B.
 ELEVATION 2454 D. F.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Soil	10
Clay, Gravel and Sand	90
Shale	860
Shale with Sand Streaks	1240
Shale and Shells	1695
Sand	1950
Shale and Shells	2152
Anhydrite	2193
Shale and Shells	2490
Shale with Lime Streaks	2540
Shale and Lime	2550
Shale with Lime Streaks	2910
Shale and Lime	3395
Shale	3510
Shale and Lime	3860
Kansas City Lime	4005
Lime and Shale	4065

FORMATION TOPS:

HEEBNER	3757
TORONTO	3780
LANSING-KANSAS CITY	3796
T. D.	4065

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *E.P. Spruick*

STATE OF KANSAS |
 | SS.
 COUNTY OF SEDGWICK |

Subscribed and sworn to before me, a notary public, in and for said County and State this 8th day of May, 1957.

Rose Lusey
 Notary Public

My Commission expires February 13, 1960.

PLUGGING
 FILE SEC. 4 T. 9 R. 24W
 BOOK PAGE 10 LINE 19

RECEIVED