


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 4 Twp. 9 Rge. 24 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines C N¹ NW SW
Lease Owner Fender Pipe & Supply
Lease Name Hildebrand Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced Aug. 16 19 65
Plugging completed Aug. 19 19 65
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well ~~XXXXXX~~ Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4050 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4050 feet to surface feet for each plug set.
Sanded up to 3970' dump 5 sacks of cement on bottom. Pulled pipe from hole run 600' of 2" circ. 35 sacks of mud, pump 30 sacks of cement to 600' pulled 2" up to 270' pump 100 sacks of cement in hole. Pulled 2" out cement was to bottom of cellar.
Well completed.

RECEIVED
STATE CORPORATION COMMISSION
9-9-65
SEP 9 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.
Address P.O. Box 313 Russell, Kansas

STATE OF Kansas COUNTY OF Russell, ss.
Allen J. Fender (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allen J. Fender
Box 302 - Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of September, 19 65

My commission expires September 27, 1967
Delma Underwood Notary Public.

CONTRACTOR'S WELL LOG

COMPANY: Artnell Company
CONTRACTOR: Leben Drilling, Inc.
FARM: Hildebrand #1
LOCATION: C. N $\frac{1}{2}$ NW SW Sec. 4-9S-24W
 Graham County, Kansas
COMMENCED: May 26, 1957
COMPLETED: June 6, 1957

0	229	Sandy Clay
229	930	Shale & Sand
930	1415	Shale & Shells
1415	1460	White Sand
1460	1565	Shale & Shells
1565	1700	Sandy Shale
1700	2000	Sand & Redbed & Shale
2000	2170	Shale & Shells
2170	2205	Anhydrite
2205	2595	Shale & Lime Streaks
2595	2729	Shale & Lime
2729	2800	Shale & Lime
2800	2880	Lime with Shale Bcks.
2880	3040	Lime & Shale
3040	3110	Shale & Lime
3110	3220	Shale & Lime
3220	3315	Shale & Lime
3315	3355	Shale & Lime
3355	3425	Shale & Lime
3425	3530	Shale & Lime
3530	3605	Shale & Lime
3605	3690	Shale & Lime
3690	3750	Shale & Lime
3750	3820	Lime & Shale
3820	3860	Lime
3860	3910	Lime
3910	3965	Lime
3965	3990	Lime
3990	4020	Lime
4020	4050	Lime
	4050	<u>Rotary Total Depth</u>

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 10 1965
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8-5/8" surface casing at 229', 150 sacks cement.

I, James M. Battin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Hildebrand #1, C N $\frac{1}{2}$ NW SW of Section 4-9S-24W, Graham County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

BY: James M. Battin

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 21st day of June, 1957.

Notary Public
 Ruth N. Benjamin

My commission expires June 17, 1961