

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20378-00-00
Spot: SENWNWNW Sec/Twnshp/Rge: 21-1S-34W
4720 feet from S Section Line, 4720 feet from E Section Line
Lease Name: SABATKA Well #: 1
County: RAWLINS Total Vertical Depth: 4381 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4356	0	w/575 sxs cmt
SURF	8.625	318	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/14/2009 11:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 265 sxs 60/40 pozmix - 4% gel - 600# hulls - 22 sxs gel.
Plug through tubing.
01/21/2009 - Ordered 150 sxs 60/40 pozmix - 4% gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/21/2009 10:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 318' w/unknown sxs cement.
4 1/2" production casing at 4356' w/575 sxs cement.
TD 4381'.
01/14/2009 - Ran tubing to 2785' - contacted solid bridge.
Pulled tubing to 2752' - pumped 90 sxs cement with 300# hulls.
Pulled tubing to 1435' - pumped 175 sxs cement with 300# hulls.
Cement to surface. Cement dropped in 4 1/2" casing.
01/21/2009 - Topped off 4 1/2" casing with 30 sxs cement.
Connected to 8 5/8" surface casing - pumped 60 sxs cement.

Perfs:

Top	Bot	Thru	Comments
4289	4292		
4253	4257		
4157	4160		

Control # 20080039001

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 26 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #044201 AND #044058.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

[Handwritten initials]

Form CP-2/3

JAN 22 2009

WILLIAM W WISE
 46 B DENVER TECH CENTER #1 SABATKA 21-1-34W
 ENGLEWOOD, CO 80211 100'NW, C NW NW
 CONTR PRAIRIE DRILLING CO CTY RAWLINS

GEOL _____ FIELD CAHOJ
 E 3200 KB CM 7/23/80 CARD ISSUED 1/15/81 IP P 4 B0 & 10 BWPD
 3189 GL LKC 4253-4292 OA
 API 15-153-20,378

+	+
+	+

LOG	TOPS	DEPTH	DATUM
ANH		3032	+ 168
RED E		3618	- 418
TOP		3902	- 702
OREAD		4002	- 802
LKC		4098	- 898
B KC		4364	-1164
RTD		4381	-1181

B-5/8" 318, 4 1/2" 4356/575sx
 DST (1) 4288-4301 (w/STR PKR)/15-45-60-90, REC 205' O SPKD M, SIP 1062-967#, FP 70-93/93-132#, HP 2177-2161#
 DST (2) 4246-4257 (w/STR PKR)/MISRUN
 DST (3) 4246-4257 (w/STR PKR)/MISRUN
 MICT - CO, PF (LKC) 4289-92, AC 500 G
 1.6 BFPH, 42% O, PF (LKC) 4253-57, AC
 500 G SWB . 7 BOPH, NW, PF (LKC) B
 4157-60, AC 350 G 7.3 BFPH, 3-5% O,
 SQZD 4157-60, POP, P 18.7 BF, EST 21%
 OIL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS