

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20895-00-01
Spot: SWSWNE Sec/Twnshp/Rge: 14-15S-21W
2970 feet from S Section Line, 2350 feet from E Section Line
Lease Name: BRENNER Well #: 2
County: TREGO Total Vertical Depth: 4246 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4242	0	125 SX
SURF	8.625	853	0	400 SX

138.00

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/26/2009 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: THAD STARR Company: AMERICAN ENERGIES CORPORAT Phone: (620) 793-2146

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 17 sxs gel.
Well had been DV'd.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/26/2009 3:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 4079'.
Allied rigged to tubing - pumped 17 sxs gel followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.
Pulled tubing to 2063'. Allied rigged to tubing - pumped 200 sxs 60/40 pozmix - 4% gel with 300# hulls to circulate cement to pit area.
Pulled tubing - topped off casing with 45 sxs 60/40 pozmix - 4% gel.
8 5/8" - pumped 5 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
4113	4122		

INVOICED
DATE 2-3-09
INV. NO. 2009061139


RECEIVED
KANSAS CORPORATION COMMISSION
JAN 28 2009

Remarks: ALLIED CEMENTING COMPANY-TICKET #34883.

Plugged through: TBG

District: 04

Signed




(TECHNICIAN)

CM

Form CP-2/3

JAN 27 2009



AMERICAN ENERGIES CORP
WICHITA KS 67202

14-15S-21W
SW SW NE

2 BRENNER OWWO

site: 7-1/2 N & 5-1/2 E OF BROWNELL KS dy: TREGO API: 15-195-20895
contr: CHEYENNE WELL SVC field: BRENNER
geol: NONE
fr date 11/09/90 spd date 11/22/97 drlg comp 11/25/97 card issued 11/09/98 last revised 11/09/98

ELV: 2265 KB, 2260 GL LOG
tops.....depth/datum
HEEB.....3646 -1381
* LANS.....3689 -1424
* BKC.....3940 -1675
* CHER.....4080 -1815
* CHER SD UPR.....4094 -1829
CHER SD LWR.....4113 -1848
* PENN CONG.....4142 -1877
MISS.....4182 -1917
LTD OLD.....4244 -1979
RTD OLD.....4246 -1981
* SAMPLE TOP

IP status:

OIL, P 6 BO & 40 BWPD, CHER 4113-4122, 01/04/98
OLD INFO: OPERATOR WAS WILD BOYS & SILVER
BULLET OIL CO, 1 FACE THE FIRE, SPD 10/07/81,
10/14/81 8-5/8" 853 / 400 SX, 5-1/2" 4242 / 125 SX, OIL, P
38 BO & 5.7 BWPD, CHER 4113-4122 OA, 10/27/81 (CARD
ISSUED 03/25/82)
CONTR: SUPREME DRILLING
NO CORES
DST (1) 4070-4106 (CHER SD UPR), / 55-60-60-120, REC
95' TF: 5' OIL, 10' OCM, 80' M ISIP 244# FSIP 244# IFP
19# -75# FFP 75# -113# IHP 1923# FHP 1904#

COPYRIGHT 1998
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

AMERICAN ENERGIES CORP
WICHITA KS 67202

14-15S-21W
SW SW NE

2 BRENNER OWWO

DST (2) 4070-4126 (CHER SD LWR), / 30-60-60-120, REC 1225' TF: 434' OIL & V SLI GCM (70%
OIL), 25' M, 704' GCO (GR 37), 62' HMCO (75% OIL) ISIP 1511# FSIP 1121# IFP 62# -338# FFP
357# -545# IHP 1923# FHP 1866#
MICT - CO, PF (CHER SD LWR) 6/4113-4116, 4/4120-4122, SO, NAT, POP, IPP 38 BOPD & 13%
WTR (GR 33), 10/27/81
NEW INFO: FR 11/09/98, RE-ENTERED 11/22/97 WSH DWN TO 4244 DC 11/25/97 CSG: PROD
CSG ALREADY IN HOLE MICT - CO, RE-PF (CHER SD LWR) 4113-4122, W / 1 SPF, AC 500
GAL, SO, SET 2-3/8" TBG AT 4051, NO PKR, POP, IPP 6 BO & 40 BWPD (GR 40), 1/4/98