

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20054-00-01
Spot: SESENE Sec/Twnshp/Rge: 25-28S-34W
3007 feet from S Section Line, 272 feet from E Section Line
Lease Name: LEMON Well #: 1-25
County: HASKELL Total Vertical Depth: 5428 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4100		WITH 2 SX CMT
PROD	4.5	5400	1015	WITH 250 SX CMT 176.41
SURF	8.625	735		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/15/2009 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: SAND TO 4125' WITH 4 SX CMT OR CIBP. PLUG AT 1880' WITH 15 SX GEL & 50 SX CMT. PLUG AT 770' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/15/2009 3:30 PM KCC Agent: LINDLEY REIMER

Actual Plugging Report:

SET CIBP @ 4100' WITH 2 SX CMT. ATTEMPTED TO CUT CASING AT 1400' DID NOT WORK. CUT CASING AT 1015'. 1ST PLUG AT 1015' WITH 15 SX GEL & 40 SX CMT. 2ND PLUG AT 740' WITH 50 SX CMT. 3RD PLUG AT 30' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5307	5318		
5220	5240		
4618	4626		
4172	4176		

INVOICED
DATE 12-3-09
INV. NO. 2009061144

KANSAS CORPORATION COMMISSION

JAN 26 2009

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

RECEIVED

Plugged through: CSG

District: 01

Signed _____

RECEIVED

JAN 22 2009

KCC DODGE CITY

(TECHNICIAN)