

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-00720-00-00
Spot: NENE Sec/Twnshp/Rge: 33-16S-10W
660 feet from N Section Line, 660 feet from E Section Line
Lease Name: STOLTENBERG Well #: 2
County: ELLSWORTH Total Vertical Depth: 3342 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S YALE # 702
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3341		150 SX
SURF	8.625	328		200 SX

108.62

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/20/2009 11:00 AM
Plug Co. License No.: 34044 Plug Co. Name: JD'S WELL SERVICE INC.
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORP Phone: (620) 793-2645

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 01/21/2009 10:15 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MOVE IN-RIG UP. PERFORATE @ 1350, 1000, AND 380'. RUN TUBING TO 3278' AND PUMP 35 SX'S CEMENT. LET SET FOR 2 HRS. TAGGED CEMENT @ 3293'. PULL TUBING TO 3061' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 3010' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 1350' AND PUMP 35 SX'S CEMENT. LET SET FOR 2 HR'S. COULD NOT RE-TAG CEMENT AFTER 2 HR'S, SO RAN TUBING BACK TO 1350' AND PUMP 35 MORE SX'S CEMENT. RE-TAGGED CEMENT @ 1220' ON 1-21-2009. PULL TUBING TO 1000' AND PUMP 35 SX'S. PULL TUBING TO 380' AND CIRCULATE CEMENT TO SURFACE. CONNECTED ON TO BACKSIDE OF PROD. CASING AND PUMPED CEMENT @ 200#'S, SHUT IN @ 100#'S. PULLED TUBING OUT AND TOPPED OFF. USED 280 SX'S TOTAL.

Perfs:

Top	Bot	Thru	Comments
3294	3314		
3013	3161		

INVOICED
DATE 2-3-09
INV NO. 2009061146

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 28 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C33232. LOG TECH TICKET #5615.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

OKT