

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20721-00-01  
Spot: SW Sec/Twnshp/Rge: 14-33S-36W  
1320 feet from S Section Line, 1320 feet from W Section Line  
Lease Name: BARBER UNIT OWWO Well #: 4  
County: STEVENS Total Vertical Depth: 6236 feet

Operator License No.: 5208  
Op Name: EXXONMOBIL OIL CORP  
Address: 14950 HEATHROW FORREST PKWY P  
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3000		
PROD	5.5	6236	1868	WITH 250 SX CMT <u>202.67</u>
SURF	9.625	1744		WITH 625 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/13/2009 8:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2575' & 2 SX CMT. PLUG AT 1780' WITH 80 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/14/2009 3:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 3000'. RIH WITH TBG TO 2575' & PUMPED 300# HULLS & 25 SX CMT. BLEW OUT CIBP. TAGGED TOC @ 3700'. RIH WITH TBG TO 2600' PUMPED 300# HULLS & 25 SX CMT. TAGGED TOC @ 2924'. 1/14/09: RIH WITH TBG TO 2500' & PUMPED 500# HULLS & 25 SX CMT. PLUG AT 1780' WITH 60 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 12 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2775	2795		
2717	2732		
2670	2690		
2634	2640		

**INVOICED**  
DATE 2-3-09  
INV. NO. 2009061148

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 29 2009

Remarks: USED COMMON CEMENT BY SARGENTS.

CONSERVATION DIVISION  
WICHITA, KS

Plugged through: CSG

District: 01

RECEIVED  
JAN 27 2009  
KCC DODGE CITY

Signed Jack Maclosky  
(TECHNICIAN)

Form CP-2/3