

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03206-00-00
Spot: SESWSE Sec/Twnshp/Rge: 13-15S-18W
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: WIESNER Well #: 3
County: ELLIS Total Vertical Depth: 3589 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3589	2308	125 SX
SURF	8.625	1159	0	500 SX

116.64

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/21/2009 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Ordered 330 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/21/2009 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

01/20/2009 - Mike's Testing sanded off bottom to 3500'. Topped with 5 sxs cement using a dump bailer.
01/21/2009 - Cut pipe at 2308' - pulled to 1650'.
Quality rigged to casing - pumped 160 sxs 60/40 pozmix - 4% gel with 300# hulls mixed in.
Pulled casing to 1175' - Quality rigged to casing - pumped 50 sxs cement with 100# hulls.
Pulled casing to 550' - Quality rigged to casing - pumped 50 sxs cement with 100# hulls.
Pulled casing to 150' - Quality rigged to casing - pumped 50 sxs cement to circulate cement into pit.
POOH. Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3573	3589	OH	

VOID

DATE: 2-3-09
INV NO. 2009061151

KANSAS CORPORATION COMMISSION
JAN 26 2009
RECEIVED

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #1099.

Plugged through: CSG

District: 04

Signed [Signature]
(TECHNICIAN) CM PCT

ISERN-WELLS

#3

WIESNER

13-15-18W
SE SW SE

Contr. / ISERN DRLG

ELLIS

County

E 1998 RBComm.

Comp. 7-28-61

IP 50 BOPD/ARB


Tops	Depth	Datum
HEEB	3248	-1250
TOR	3270	-1272
LANS	3298	-1300
ARB	3571	-1573
TD	3589	-1591

Casing
8" 1159
5" 3589

DST 3299-3330/1 HR, 10' M, F
SPKS 0, BHP 0#

DST 3448-65/1 HR, 5' M, NS
CO 3575: NS: DD 3582: ACID 500:
SWB 2 BOPH: DD 3589: ACID 1000:
SWB 21 BOPH

LEIKER EAST POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS