

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03208-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 13-15S-18W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: WIESNER Well #: 5
County: ELLIS Total Vertical Depth: 3616 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3600		
PROD	5.5	3615	2310	200 SX <u>117.52</u>
SURF	8.625	1189	0	400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/23/2009 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Ordered 330 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2009 10:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Sanded off bottom to 3300'. Topped with 5 sxs cement using a dump bailer.
Pulled casing to 1650'. Quality rigged to casing - pumped 160 sxs cement with 300# hulls mixed in.
Pulled casing to 1170'. Quality rigged to casing - pumped 50 sxs cement with 100# hulls.
Pulled casing to 540'. Quality rigged to casing - pumped 50 sxs cement with 100# hulls.
Pulled casing to 150'. Quality rigged to casing - pumped 50 sxs cement to circulate cement to pit area.
POOH. Pulled casing - hole standing full.

Perfs:

Top	Bot	Thru	Comments
3615	3620	OH	ARBUCKLE
3364	3368		KANSAS CITY

INVOICED
DATE 2-3-09
INV NO. 200906151

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 27 2009


CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #3177.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

JAN 23 2009

ISERN-WELLS

#5 WIESNER

13-15-18W
NW SW SE

Contr. ISERN-WELLS

ELLIS

County

E1989 RB Comm.

Comp. 8-25-61

IP 110 BOPD/ARB

Tops	Depth	Datum
HEEB	3233	-1244
LANS	3283	-1295
ARB	3558	-1569
TD	3616	-1627

Casing

8" 1189

5" 3615

DST 3290-3314/1 HR, 6' M, BHP
0#

CO 3590: PERF 16/3564-68: SWB

2 BOPH, NATL: ACID 500: HFW:

SQZ: 8/3592-94: 8/3564-68: ACID

250: 3000' OIH/12 HRS: SWB 8

LEIKER EAST POOL BOPH

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS