

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-21062-00-00  
Spot: SEWSE Sec/Twnshp/Rge: 17-12S-17W  
1631 feet from S Section Line, 1724 feet from E Section Line  
Lease Name: MILLER A Well #: 1  
County: ELLIS Total Vertical Depth: 3708 feet

Operator License No.: 7383  
Op Name: GRADY BOLDING CORPORATION  
Address: PO BOX 486  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		1450		375 SX
PROD	4.5	3700	0	100 SX
SURF	8.625	240	0	125 SX

120.51

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/16/2009 12:45 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 4% gel - 500# hulls.  
DV tool at 1450' w/375 sxs.  
Low fluid level.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/16/2009 1:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality Oilwell Service rigged to 4 1/2" casing - pumped 35 sxs 60/40 pozmix - 4% gel with 250# hulls.  
Mixed and pumped 9 sxs gel.  
Mixed and Pumped 100 sxs 60/40 pozmix - 4% gel with 250# hulls.  
Max. P.S.I. 1000#. S.I.P. 300#.  
Rigged to 8 5/8" casing - pumped 5 sxs cement.  
Max. P.S.I. 400#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3702	3708		



RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 23 2009  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
DATE 2-3-09  
NW NO 2009061151

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #3003.

Plugged through: CSG

District: 04

Signed  (TECHNICIAN) 

JAN 20 2009

LSERN PETROL. CO.  
BOX 486, ELLINWOOD, KS.  
CONTR DUKE DRILG. CO.

#1 MILLER "A"

17-12-17W  
SE NW SE

CTY. ELLIS

GEOL \_\_\_\_\_ FIELD BEMIS-SHUTTS EXT

E 2151 KB CM 6/3/75 <sup>CARD</sup> ISSUED 7/24/75 IP P 15 BOPD + 75% W  
ARB 3698-3708

+	+	+
+	+	+

API 15-051-21,062

SMP	TOPS	DEPTH	DATUM
ANH		1369	+ 782
HEFB		3370	-1219
LKC		3418	-1267
CONG		3663	-1512
SIMP SH		3680	-1529
ARB		3698	-1547
RTD		3702	-1551
DDTD		3708	-1557

8 5/8" 240/125SX, 4 1/2" 3700 1/2/100SX

DV W/375SX

NO DST'S

NO LOG

MICT - DD 3703, FU 750' FL, A 250 MA,  
DD 3708, A 1000, SWB 5 BFPH, 60% WTR,  
POP

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS