

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-23340-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 16-12S-20W  
990 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: NICHOLSON B Well #: 3  
County: ELLIS Total Vertical Depth: 3947 feet

Operator License No.: 7383  
Op Name: GRADY BOLDING CORPORATION  
Address: PO BOX 486  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3936	1008	150 SX
SURF	8.625	932	0	375 SX

128.28

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/16/2009 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Ordered 280 sxs 60/40 pozmix - 4% gel - 500# hulls.  
LK Wireline perfed at 2050' and 1665'.  
No bridge plugs.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/16/2009 10:30 AM KCC Agent: PAT STAAB

**Actual Plugging Report:**

01/15/2009 - Mike's Testing sanded off bottom to 3800'. Topped with 4 sxs cement.  
Pulled 4 1/2" casing - parted at 1008'.  
01/16/2009 - LK Wireline perfed at 2050' and 1665'.  
Mike's Testing RIH with tubing to 2050'.  
Quality Oilwell rigged to tubing and pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 1665'. Quality Oilwell rigged to tubing - pumped 40 sxs cement with 100# hulls.  
Pulled tubing to 950'. Quality Oilwell rigged to tubing - pumped 90 sxs cement with 100# hulls.  
Pulled tubing to 200'. Quality Oilwell rigged to tubing - pumped 80 sxs cement with 100# hulls-mixed in to circulate cement to pit.  
POOH. Pulled tubing - topped off with 20 sxs cement.  
Hole standing full.

**Perfs:**

Top	Bot	Thru	Comments
3872	3882		

**RECEIVED**  
KANSAS CORPORATION COMMISSION  
**JAN 23 2009**  
CONSERVATION DIVISION  
WICHITA, KS

**INVOICED**  
DATE 2-3-09  
INV. NO. 2009001151

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #3001.

Plugged through: TBG

District: 04

Signed




(TECHNICIAN)

CM

Form CP-2/3

JAN 20 2009



N-B COMPANY, INC.

P.O. BOX 506

RUSSELL, KS 67665-0506

CONTR COMPANY TOOLS

#3 "B" NICHOLSON

CTV ELLIS

16-12-20W

NE SW SW

GEOL \_\_\_\_\_

FIELD DIST. 57 NO.


ELV 2251 KB SPD 2/18/83

CARD ISSUED 4/28/83

IP P 34 BOPD & TR WTR

API 15-051-23,340

MARM 3872-3882



LOG	Tops	Depth/Datum
SC	1618 + 633	
TOP	3300-1049	
HEEB	3531-1280	
TOR	3552-1301	
LANS	3570-1319	
BKC	3815-1564	
MARM	3862-1611	
RTD	3947-1696	

8 5/8 " 932/375SX; 4 1/2 " 3936

NO DSTS

MICT - CO, PF (MARM) 3872-82, AC 1000G, SWB 2 BFPH (80% OIL) / 5 HRS, FU 400' FL (75% OIL) / 14 HRS, FRAC 13,000# SD & NITROGEN, SWB 11 BFPH (30% OIL) / 2 HRS, SWB 7 BOPH / 6 HRS, R&T, POP, P 34 BOPD & TR WTR, 3/20/83

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS