

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20488-00-00

Spot: SWNENE

Sec/Twnshp/Rge: 6-25S-17W

990 feet from N Section Line,

990 feet from E Section Line

Lease Name: JIMMIE

Well #: 1-6

County: EDWARDS

Total Vertical Depth: 4517 feet

Operator License No.: 31938

Op Name: INDIAN OIL CO., INC.

Address: PO BOX 209 2507 SE US 160 HWY
MEDICINE LODGE, KS 67104

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2230		WITH 2 SX CMT

CIBP		2352		
------	--	------	--	--

CIBP		2788		
------	--	------	--	--

CIBP		4390		
------	--	------	--	--

PROD	4.5	4515	628	WITH 200 SX CMT
------	-----	------	-----	-----------------

SURF	8.625	599		WITH 350 SX CMT
------	-------	-----	--	-----------------

1416.80

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 01/22/2009 11:50 AM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: ANTHONY FARRAR

Company: INDIAN OIL CO.

Phone: (620) 886-3763

Proposed
Plugging
Method:

CIBP @ 2230' WITH 2 SX CMT. PLUG AT 1590' WITH 50 SX CMT. PLUG AT 650' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 01/22/2009 1:15 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 2230' WITH 2 SX CMT. 1ST PLUG PLUG RAN TBG TO 690' & PUMPED 10 SX GEL - 60 SX CMT. 2ND PLUG PULLED TBG TO 60' & PUMPED 60 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4472	4476		
2792	2806		
2779	2786		
2463	2467		
2411	2415		
2377	2381		
2362	2366		
2293	2397		
2277	2281		

INVOICED

DATE

2-3-09

INV. NO.

2009061153

KANSAS CORPORATION COMMISSION

JAN 26 2009

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

JAN 23 2009

KCC DODGE CITY

Signed

Richard M. Lacey

(TECHNICIAN)