

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22195-00-01
Spot: NWNWNE Sec/Twnshp/Rge: 5-15S-13W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: GROSS A Well #: 2
County: RUSSELL Total Vertical Depth: 638 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 83RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		378		
PROD	5.5	638	0	w/unknown sxs cmt
SURF	10.75	705	0	w/unknown sxs cmt <u>35.00</u>
T1	2.875	378		

Well Type: SWD UIC Docket No: D22524.0 Date/Time to Plug: 01/13/2009 2:00 PM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: DAVID FUNK Company: JASON OIL COMPANY, LLC Phone: (785) 324-1041

Proposed
Plugging
Method:

Ordered 200 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/13/2009 3:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Hooked up to backside. Pressured up to P.S.I. 800#. Full.
Hooked up to casing - pumped 50 sxs 60/40 pozmix - 4% gel with zero hulls.
Pumped 80 sxs 60/40 pozmix - 4% gel with 500# hulls.
Max. P.S.I. 500#. S.I.P. 200#.

Perfs:

Remarks: QUALITY OILWELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM
PKT

Form CP-2/3

JAN 20 2009

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 23 2009
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 2-3-09
INV. NO. 2009061154

HERMAN TRAPP
324 FRONT

#2 "A" GROSS "OW/O"

5-15-13W
NW NW NE


RUSSELL, KS 67665

CONTR SUPER OILWELL SERVICE

CTY RUSSELL

GEOL

FIELD HALL-GURNEY



ELV 1739 GL SPD 8/18/83 CARD ISSUED 1/12/84

IP SWDW
CED HILLS - INTV NA

API 15-167-22,195-A

SMP	Tops	Depth/Datum
ANH	685	+1054
LANS	2872	-1133
CONG	3175	-1436
PBTD	2887	-1148
RTD	3217	-1478

OLD INFO: OPERATOR WAS C. TRAPP, #3 "A" GROSS 'TWIN', SPD 10/19/49, SET 15" 118, 5 1/2 " 3191, COMP. AS P 18 BOPD & 40% WTR, LKC 2900-2915, 1/13/50 (CARD ISSUED 1/13/50), CONTR: UNKNOWN
 MICT - CO, PB 2887 TD, PF (LKC) 56 / 2900-2915, AC 9000 G, SWB DWN, POP

NEW INFO: FR 8/17/83, RE-ENTERED EST 8/18/83, WSH DWN TO 640, SET 5 1/2 " 640/225 SX, MICT - CO, PF (CED HILLS) INTV NA, SWDW - INJECTION RATE SATISFACTORY - TIGHT HOLE - NO OTHER INFO TO BE RELEASED AT PRESENT - WILL RELEASE INFO WHEN AVAILABLE - TEMP COMP - 1/12/84

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS