

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-25260-00-00  
Spot: NENWSWNE Sec/Twnshp/Rge: 5-16S-14W  
1470 feet from N Section Line, 2115 feet from E Section Line  
Lease Name: NUSS B Well #: 1  
County: BARTON Total Vertical Depth: 3480 feet

Operator License No.: 5135  
Op Name: FARMER, JOHN O., INC.  
Address: 370 W WICHITA AVE PO BOX 352  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	432		200 SX

113.10

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/16/2008 8:00 AM  
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC  
Proposal Rcvd. from: DOUG Company: FARMER, JOHN OIL, INC. Phone: (785) 483-3144

Proposed Plugging Method: Ordered 185 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 10/16/2008 4:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st. Plug at 3380' w/25 sxs.  
2nd. Plug at 950' w/25 sxs.  
3rd. Plug at 475' w/80 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Perfs:

RECEIVED  
DATE: 2-3-09  
TRV. NO. 2009061155

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 20 2009

CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING.

Plugged through: DP

District: 04

Signed Case Morris  
(TECHNICIAN)

Form CP-2/3

JAN 16 2009

PKS