

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-19101-00-01  
Spot: SWSWNW Sec/Twnshp/Rge: 27-20S-13W  
2970 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: SANDROCK UNIT Well #: C-1  
County: BARTON Total Vertical Depth: 3626 feet

Operator License No.: 3273  
Op Name: LOEB, HERMAN L.  
Address: PO BOX 524  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3550	0	w/unknown sxs cmt
SURF	8.625	230	0	w/unknown sxs cmt <u>117.85</u>

Well Type: EOR UIC Docket No: E23285.3 Date/Time to Plug: 01/20/2009 10:00 AM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: M.L. COX Company: LOEB, HERMAN L. Phone: (618) 943-2227

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 15 sxs gel.  
Perfed at 1600' and 725'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/20/2009 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3250'- tied to tubing - pumped 15 sxs gel - pumped 60 sxs cement with 200# hulls.  
Pulled tubing to 1600'- tied to tubing - pumped 100 sxs cement with 150# hulls.  
Pulled tubing to 800'- tied to tubing - pumped 100 sxs cement with 150# hulls - circulated to surface.  
Pulled tubing - tied to casing - pumped 10 sxs cement.  
Max. P.S.I. 500#. Shut in.  
Note: Records indicate backside had been squeezed and was full to surface.

Perfs:

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 23 2009  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
DATE 2-3-09  
INV. NO. 2009061156

Remarks: ALLIED CEMENTING COMPANY-TICKET #33336.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

Form CP-2/3

JAN 20 2009

PKG