

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21521-00-00
Spot: NESENW Sec/Twnshp/Rge: 29-30S-18W
1570 feet from N Section Line, 2310 feet from W Section Line
Lease Name: COBB A Well #: 3-29
County: KIOWA Total Vertical Depth: 3600 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3589	2430	WITH 125 SX CMT
SURF	8.625	741		WITH 320 SX CMT

117.00

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/21/2009 3:25 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 3450' & 4 SX CMT. PLUG AT 1140' WITH 15 SX GEL 50 SX CMT 100# HULLS. PLUG AT 780' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/21/2009 5:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SAND BACK TO 3450' & 4 SX CMT. 1ST PLUG AT 1140' WITH 15 SX GEL, 50 SX CMT, 100# HULLS. 2ND PLUG AT 780' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3504	3514		

INVOICED
DATE 2-3-09
INV. NO. 2009061157

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 28 2009

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
JAN 22 2009
KCC DODGE CITY

Form CP-2/3

PKT