

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21391-00-00  
Spot: NWSE Sec/Twnshp/Rge: 6-33S-5W  
1980 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: EILEEN SALSER Well #: 1-6  
County: HARPER Total Vertical Depth: 4470 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4456	2503	235 SX CMT
SURF	8.625	305		175 SX CMT

145.28

Well Type: ~~GAS~~ Oil KCCPKT for ACO-1 UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/11/2008 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CO Phone: (316) 682-1537

Proposed Plugging Method: SAND BACK TO 4320 AND CAP WITH 4 SKS OF CMT. REC. PIPE. 35 SKS 950', 35 SKS 650', CIRC 350-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/11/2008 10:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4320' AND CAPPED WITH 2 SKS OF CMT. THE CASING WAS RECERED FROM 2503', AND PULLED TO 950', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 650, WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 350', WHERE CMT WAS CIRC TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4371	4381		

1-28-09  
2009061128

RECEIVED  
KANSAS CORPORATION COMMISSION  
  
JAN 13 2009  
  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: CONSOLIDATED CMTG 60/40 POZ

Plugged through: CSG

District: 02

Signed [Signature]  
(TECHNICIAN) [Signature]