

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-20213-00-00
Spot: SWNE Sec/Twnshp/Rge: 6-34S-4W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease Name: NETAHLA Well #: 1
County: SUMNER Total Vertical Depth: 4805 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4804	500	125 SX
SURF	8.625	250		225 SX

156.14

Well Type: GAS oil KCCPT UIC Docket No: _____ Date/Time to Plug: 12/07/2008 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CO. Phone: (316) 682-1537

Proposed Plugging Method: CIBP @ 4690' AND 2 SKS, RECOVER PIPE, 35 SKS 850', 35 SKS 550', CIRC CMT 300-0

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/08/2008 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE WELL HAD JUNK IN HOLE AT 4725', A CIBP WAS SET AT 4690' AND CAPPED WITH 2 SKS OF CMT. THE CASING WAS RECOVERED FROM 1973' AND PULLED TO 1471', WHERE THE WELL KICK OFF. THE WELL WAS SHUT IN. 2-80 BBL LOADS OF DRILLING MUD WAS PUMPED 100 SKS OF CMT, DISPLACED CMT TO 1370', AND LEFT WELL SHUT IN OVER WEEKEND. 12-8-2008. WELL DEAD. PERD CASING AT 847', AND PUMPED 50 SKS OF CMT. PERFD CASING AT 550' AND PUMPED 50 SKS OF CMT. PERFD CASING AT 300', AND CIRCD CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4734	4738		

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 13 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: CONSOLIDATED CMT 60/40 4% AND COMMON

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)

PKT