

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

Complete Perms
API Well Number: 15-097-20754-00-02
Spot: ~~N2NWSWSW~~ *OK* Sec/Twnshp/Rge: 12-28S-16W
~~4407~~ *OK* 1300 feet from S Section Line, 4950 feet from E Section Line
Lease Name: WELLSFORD TOWNSITE ~~5087~~ Well #: 1
County: KIOWA Total Vertical Depth: 4775 feet

Operator License No.: 31739
Op Name: IUKA-CARMI DEVELOPMENT LLC
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	4585		
PROD	4.5	4774	2450	
SURF	8.625	409		WITH 275 SX CMT

155.19

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/01/2008 11:50 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: GARELD INSLEE Company: IUKA-CARMI DEVELOPMENT Phone: (620) 672-2531

Proposed Plugging Method: SAND TO 4490' WITH 4 SX CMT. PLUG AT 1080' WITH 15 SX GEL, 200# HULLS, & 50 SX CMT. PLUG AT 450' WITH 200# HULLS & 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2008 1:05 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SAND BACK TO 4490' WITH 4 SX CMT. 1ST PLUG AT 1080' WITH 15 SX GEL, 75# HULLS, & 50 SX CMT. 2ND PLUG AT 450' WITH 75# HULLS & 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4692	4694		
4677	4679		


INVOICED
DATE 1-8-09
INV. NO. 2009060946

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 08 2008

Remarks: USED 60/40 POZMIX 4% GEL 2%CC BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01



Signed *Eric MacLaren*
(TECHNICIAN)

PKT
OB