

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-051-03413-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 11-30-42(completion date)

Well Operator: Lario Oil & Gas KCC License #: 5214
(Owner / Company Name) (Operator's)
Address: 301 S. Market City: Wichita
State: Kansas Zip Code: 67202 Contact Phone: (316) 265-5611
Lease: Marshall A Well #: 13 SWD Sec. 31 Twp. 11 S. R. 17 East West
C - SW - NW - _____ Spot Location / QQQQ County: Ellis

1980 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
660 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # D-747 ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8" Set at: 1355 Cemented with: 350 Sacks
Production Casing Size: 5 1/2" Set at: 3757 Cemented with: 1600 Sacks

List (ALL) Perforations and Bridgeplug Sets: Open hole completed

Elevation: 2108' (G.L. / K.B.) T.D.: 4200' P.B.T.D.: _____ Anhydrite Depth: 1344'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): 1). Run tubing to 3,000'. Pump 140 sks 60/40 poz, 4% get and 300 pounds of hulls. 2). Pull tubing to 2,500'. Pump 9 sks of gel. 3). Pull tubing to 2,000'. Circulate cement w/205 sks and 200 pounds of hulls. 4). Pull tubing, install casing swage and squeeze hole with 25 sks of cement. 5) estimate 55 sks for backside.(per Pat Staab).

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Well completed in 1942

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: David L. Jensen

Phone: (785) 625-5023

Address: Box 784 City / State: Hays, Kansas

Plugging Contractor: Lario Oil & Gas KCC License #: 5214
(Company Name) (Contractor's)

Address: Box 784, Hays, Kansas 67601 Phone: (785) 625-5023

Proposed Date and Hour of Plugging (if known?): Unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1-29-09 Authorized Operator / Agent: David L. Jensen (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Dist 4
PCT

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 30 2009

CONSERVATION DIVISION
WICHITA KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

LARIO OIL & GAS COMPANY
301 S MARKET ST
WICHITA, KS 67202-3805

February 04, 2009

Re: MARSHALL A #13 SWD
API 15-051-03613-00-00
31-11S-17W, 3257 FSL 4704 FEL
ELLIS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after August 3, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550