

RECEIVED
KANSAS CORPORATION COMMISSION

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

FORM CP-1
September 2003
This Form must be Typed
Form must be Signed
All Blanks must be filled

FEB 03 2009

CONSERVATION DIVISION
WICHITA, KS

WELL PLUGGING APPLICATION
PLEASE TYPE FORM and File ONE Copy

API #: 15-135-23565 - 00-60 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued,

Indicate spud or completion date: _____

Well Operator: American Energies Corporation KCC LICENSE # 5399
(owner/company name) (operator's)

Address: 155 North Market CITY: Wichita

State: Kansas Zip Code: 67202 Contact Phone: 316-263-5785

Lease: Ummel Trust Well #: 1 Sec. 26 Twp. 16 S R. 22W

70'E of C SW SW SE Spot Location/QQQQ County: Ness

349 ~~FNL~~ Feet (in exact footage) From _____ North/ South (from nearest outside section corner) Line of Section (Not Lease Line)

2232 ~~FNL~~ Feet (in exact footage) From East / _____ West (from nearest outside section corner) Line of Section (Not Lease Line)

KCC 1/14
Per 1
CP 2/13

Check One: Oil Well Gas Well _____ D&A _____ Cathodic _____ Water Supply Well _____
SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks _____

Surface Casing Size: 8 5/8" Set at: 262.68' Cemented with: 150 Sacks _____

Production Casing Size: 5 1/2" Set at: 4409' Cemented with: 150 Sacks _____

List (ALL) Perforations and Bridgeplug Sets: Perforated Cherokee Sand 4302-4306 w/10 SPF

Elevation: 2387 GL T.D. 4410' PBTD: _____ Anhydrite Depth: 1700'

(Stone Corral Formation)

Condition of Well: Good Poor _____ Casing Leak _____ Junk in Hole _____

Proposed Method of Plugging (attach a separate page if additional space is needed):

Spot sand over perms - 4302-4306, 25 sx cement at perms with 200 sx hulls. Fill to 1650' with mud, spot 25 sx cement plug.

Fill to 1,000' with mud, pump cement to surface.

Tie on annulus, try and displace 50 sx cement down backside, if it will take it.

Is Well Log attached to this application as required? No (Yes/No) Is ACO-1 Filed? Yes (Yes/No)

If Not explain why? Currently on file with state

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. Seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Thad Starr, Production Superintendent

Phone: 620-793-2146

Address: 155 North Market, Suite 710 City: Wichita State: KS

Plugging Contractor: Allied Cermenting KCC LICENSE #: N/A

(company name) (contractor's)

Address: P.O. Box 31 City: Russell State: Kansas Zip _____

Proposed Date and Hour of Plugging (if known?): _____ Within the next two weeks

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 01/20/09 Authorized Operator/Agent: Alan L. DeGood

(signature) Alan L. DeGood, President

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Dist 1
PWA



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

AMERICAN ENERGIES CORPORATION
155 N MARKET STE 710
WICHITA, KS 67202-1821

February 04, 2009

Re: UMMEL TRUST #1
API 15-135-23565-00-00
26-16S-22W, 349 FSL 2232 FEL
NESS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after August 3, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888