

RECEIVED
NOV 14 2002
KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-175-21117-00-01 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Chesapeake Operating, Inc. KCC LICENSE # 32334 ^{4/03}
(owner/company name) (operator's)

ADDRESS P. O. Box 18496 CITY Oklahoma City

STATE OK ZIP CODE 73154-0496 CONTACT PHONE # (405) 848-8000

LEASE Dreitz Farms OWO WELL# 1-4 SEC. 4 T. 32S R. 33W (East/West)

- SE - SE - NE SPOT LOCATION/QQQQ COUNTY Seward

2962 FEET (in exact footage) FROM (S)N (circle one) LINE OF SECTION (NOT Lease Line)

386 FEET (in exact footage) FROM (E)W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8 SET AT 1608' CEMENTED WITH 750 SACKS

PRODUCTION CASING SIZE 4-1/2" SET AT 5768' CEMENTED WITH 200 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 5528-34' Morrow; 5542-702' Chester;

ELEVATION KB: 2892' T.D. 5952' PBDT 5725' ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE: _____

PROPOSED METHOD OF PLUGGING Set CIBP @5480 & cap w/20' cmt, displace hole w/9 ppg abandonment mud to ± 1660'. Cut off 4-1/2" csg @1560' to set 100' cmt plug from 1660'-1560'. displace surface csg w/9 ppg abandonment mud & cap w/50' of cement to surface.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bud Neff PHONE# (620) 277-0803

ADDRESS 4532 W. Jones Avenue City/State Garden City, KS 67846

PLUGGING CONTRACTOR Allied Cementing KCC LICENSE # _____
(company name) (contractor's)

ADDRESS P. O. Box 31, Russell, KS PHONE # (785) 483-3387

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 11/12/02 AUTHORIZED OPERATOR/AGENT: Randy Gasaway
(signature) Randy Gasaway