

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-05506665-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 8/03

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)
ADDRESS 701 S. TAYLOR, STE 400 CITY AMARILLO
STATE TEXAS ZIP CODE 79101 CONTACT PHONE (806) 457-4600
LEASE OHMES WELL# 1 SEC. 22 T. 26S R. 32 (xxxx/West)
- SW - SW - NE SPOT LOCATION/QQQQ COUNTY FINNEY

2310 FEET (in exact footage) FROM X (N) (circle one) LINE OF SECTION (NOT Lease Line)
2310 FEET (in exact footage) FROM (E)X (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS
SURFACE CASING SIZE 10-3/4" SET AT 500 CEMENTED WITH 850 SACKS
PRODUCTION CASING SIZE 7" SET AT 2762 CEMENTED WITH 375 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: PERFS: 2664-2677, 2685-2708, 2718-2744
ELEVATION 2879 / xx T.D. 2763 PBD 2762 ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING DUMP 43 SXS CLASS H CMT TO PLUG FROM 2762 TO 3560.
DISPLACE WITH 9 PPG MUD. SPOT 65 SXS CLASS H CMT PLUG AT 1000 TO 700. DISPLACE WITH 9
PPG MUD. SPOT 10 SXS CLASS H CMT FROM 40 TO 4. CUT OFF AND CAP 10-3/4" AND 7" CSG 4'
BELOW GL.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

DAVID RELEFORD PHONE# (620) 482-1000
ADDRESS 1707 W 2ND City/State LIBERAL, KS

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)
ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515 1/03

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 10/3/2002 AUTHORIZED OPERATOR/AGENT: Craig R. Walters
LO: 1 07 107 OCT 7 2002 CRAIG R. WALTERS, P.E. (Signature)
DIVISION PRODUCTION ENGINEER

RECEIVED
KANSAS CORP COM