


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County, Sec. 32 Twp. 11 Rge. 16 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NW NE SE
Lease Owner Shields Oil Producers
Lease Name Chrisler Well No. 1
Office Address Shields Building, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 6 1958
Application for plugging filed August 6 1958
Application for plugging approved August 6 1958
Plugging commenced August 6 1958
Plugging completed August 6 1958
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3456 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	302'	Cmtd. w/175 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill w/heavy mud to 200'
Set bridging plug @ 300' w/1/2 sax hulls
Dump 20 sax cement thru drill pipe on plug
Fill w/heavy mud to 35'
Set bridging plug @40' w/1/2 sax hulls
Dump 10 sax cement on plug to cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Co., Inc.
Address Shields Bldg., Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
R. J. Shields (~~employee of owner~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. J. Shields
Shields Bldg., Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 1958

My commission expires March 6, 1961

REC-FILED
STATE CORPORATION COMMISSION
AUG 12 1958
8-12-1958
CONSERVATION DIVISION
Wichita, Kansas

Notary Public
HARRIET V. PETERSON

PLUGGING
FILE SEC 32 T. 11 R. 16w
BOOK PAGE 122 LINE 16



Shields


15-051-01220-00-00

Russell, Kansas

WELL LOG

Operator: Shields Oil Producers
 Well: Chrisler #1
 Commenced: July 27, 1958
 Completed: August 7, 1958
 Contractor: Shields Drilling Co., Inc.

Well Description: NW NE SE
 Sec. 32-11S-16W
 Ellis County, Kansas



Elevation: 1881' RB

Treatment:

Production: D & A

CASING RECORD

Size	Run	Pulled
8 5/8"	302'	Cmtd. w/175 sax.

Tops: Heebner 3048'
 Toronto 3075'
 Lansing - K. C. 3098'
 Marmaton 3336'
 Conglomerate Sand 3388'
 Cherty Conglomerate 3404'

..... Figures Indicate Bottom of Formations

Shale & Shells	302'
Shale; Shells; Sand	520'
Shale & Shells	590'
Sand	715'
Red Bed; Sand; Shale & Shells	1040'
Anhydrite	1075'
Shale & Shells	1495'
Shale; Shells & Lime	1700'
Broken Lime	1900'
Shale	2035'
Broken Lime	2280'
Shale & Lime	2365'
Broken Lime; Shale	2495'
Lime & Shale	2890'
Lime	2950'
Shale & Lime	3099'
Lansing Lime	3130'
Shale & Lime	3185'
Lime	3270'
Lime & Shale	3370'
Lime; Shale & Sand	3400'
Lime & Shale	3405'
Lime; Chert; Shale & Cong.	3456' RTD

PLUGGING	
FILE	SEC. 32 T. 11 R. 16W
BOOK	PAGE 122 LINE 16

RECEIVED
 STATE CORPORATION COMMISSION
 8-12-1958
 AUG 12 1958
 CONSERVATION DIVISION
 Wichita, Kansas

Notes

DST #1

3374' - 3400'

Tool open 30 min. w/weak blow for 1 min.
 Rec. 6' mud. BHP-128#/20 min.