


15-051-00190-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis County, Sec. 33 Twp 11S Rge. 16 (NW) (W)
Location as "NE/CNW/SW" or footage from lines. NW NW NW



Lease Owner Heathman & Company
Lease Name Chrisler Well No. 1
Office Address 254 N. Washington Wichita Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-2 19 53
Application for plugging filed 8-2 19 53
Application for plugging approved 8-2 19 53
Plugging commenced 8-2 4.00 P. M. 19 53
Plugging completed 8-2 8:00 P. M. 19 53
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes Verbal

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3433 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand, Blue shale, Shells, & Redbed		0	760'	8 5/8	760'	None
Lime & Shale		760	2780			
Lime		2780	3360			
Conglomerate		3360	3370			
Chirty Conglomerate		3370	3433			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Stirred pits well filled hole with heavy mud, set bottom wood plug @ 300', Ran 1/2 sack hulls and 25 sacks of cement on same. Filled hole with heavy mud to 40' set top plug. Ran 1/2 sack hulls and 10 sacks of cement filling to the bottom of the cellar.

RECEIVED
STATE CORP. COM.
AUG 18 1953

Name of Plugging Contractor Strain Drilling Company
Address Box 188 Hays, Kansas.

STATE OF Kansas, COUNTY OF Ellis, ss.
T. C. Strain (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. C. Strain
Box 188 Hays, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 53

Mildred Schneider
Notary Public.

My commission expires March 26, 1956

24-2675-S 2-52-20M

PLUGGING
FILE SEC 33 T 11 R 16W
BOOK PAGE 120 1111-9

15-051-00190-00-00

WELL LOG

COMPANY: Heatman & Company

NW NW NW Sec. 33
Twp 11S Rge 16W
Ellis County, Kansas.

LEASE: Chrysler # 1

ELEVATION: 1828 R. B.

NOTE: All meas Rotary Bushing

0	20 Soil & Shale
20	65 Postrock
65	245 Blue Shale & Shells
245	270 Shale & Shells
270	290 Sand & Shale
290	390 Shale, Shells & Sand
390	495 Sand & Shale
495	530 Shale
530	650 Sand DK
650	754 Shale, Shells & Redbed
754	775 Redbed
775	992 Shale, Shells & Redbed
992	1030 Anhydrite
1030	1320 Shale & Shells
1320	1600 Shale & Shells
1600	1630 Lime & Shale
1630	1690 Lime & Shale
1690	1710 Lime
1710	1945 Lime & Shale
1945	2005 Lime & Shale
2005	2020 Lime
2020	2060 Lime
2060	2245 Lime & Shale
2245	2385 Lime & Shale
2385	2500 Lime & Shale
2500	2635 Lime & Shale
2635	2780 Lime & Shale
2780	2830 Lime
2830	2880 Lime
2880	2915 Lime
2915	2955 Lime
2955	3005 Lime
3005	3052 Lime
3052	3090 Lime
3090	3135 Lime
3135	3160 Lime
3160	1395 Lime
3195	3225 Lime
3225	3265 Lime

3265	3310 Lime
3310	3360 Lime
3360	3370 Conglomerate
3370	3410 Chirty Conglomerate
3410	3433 Chirty Conglomerate
3433	(Total Depth)

COMMENCED: 7-21-53
COMPLETED: 8-2-53

CASING RECORD:

8 5/8 Surface Casing set at 760' w/400 sacks of cement by Sun Cementing Co.

D.S.T. by Johnston Testers

3330-3365 Tool open 1 hour. Recovered 40' of watery mud. Weak blow 1 hour. 20 min B.H.P. 880#

Schlumberger Logs Run

Geologist: Bob Armstrong

TOPS:

Geological

Anhydrite	992 (+836)
Topeka	2756 (- 928)
Heebner	3000 (-1172)
Toronto	3022 (-1194)
	T. D. 3433 (-1605)

Lansing	3047 (-1219)
Base K. C.	3270 (-1442)
Conglomerate	3337 (-1509)
Arbuckle	3423 (-1595)

STATE OF KANSAS) SS
COUNTY OF ELLIS)

STATE OF KANSAS

8-18-1953

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Chrysler # 1, located NW NW NW, Sec.33, Twp 11S, Rge. 16W Ellis County, Kansas.

CONTRACTOR: Strain Drilling Company

BY: T. C. Strain
T. C. Strain

PLUGGING
SEC 33 T. 11 S. R. 16 W.
WELL NO. 1

Subscribed and sworn to before me this 5th day of August 1953
My commission expires March 26, 1956

Mildred Schneider
Notary Public