


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

WELL PLUGGING RECORD

15-051-70630-00-00
01053

Ellis County, Sec. 12 Twp. 11S Rge. 17W (W)
Location as "NE/CNW/SW" or footage from lines. NW 1/4 NE 1/4 SE 1/4
Lease Owner Leben Drilling, Inc.
Lease Name Cress Well No. 1
Office Address 905 Central Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-20-57 19
Application for plugging filed 11-20-57 19
Application for plugging approved 11-20-57 19
Plugging commenced 11-20-57 19
Plugging completed 11-20-57 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	980'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole with heavy mud to 430'. Set plug with 1/4 sack hulls & 20 sacks cement, filled w/ heavy mud to 240' with 1/4 sack hulls & 20 sacks cement. Top plug @ 35' with 1/4 sacks hulls and 10 sacks cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
11-27-1957
NOV 27 1957

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Frank Hamlin, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin
905 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of November, 19 57

My commission expires June 17, 1961

Arthur G. Benjamin
Notary Public.

PLUGGING
FILE SEC. 12 T. 11 R. 17W
BOOK PAGE 63 LINE 31

DRILLER'S LOG

COMPANY: LEBEN DRILLING, INC.
CONTRACTOR: LEBEN DRILLING, INC.
FARM: CRESS #1
LOCATION: NW $\frac{1}{4}$ NE $\frac{1}{4}$ SE $\frac{1}{4}$ SEC. 12-11S-17W
ELLIS COUNTY, KANSAS
COMMENCED: 11-9-57
COMPLETED: 11-20-57

0	430	Shale, Clay & Sand		
430	610	Sand & Shale		
610	830	Redbed, Shale & Shells		
830	973	Shale & Redbed	TOPS:	
973	980	Anhydrite	ANHYDRITE	973
980	1015	Anhydrite	HEEBNER	2927
1015	1175	Redbed & Shale	TORONTO	2947
1175	1645	Shale	LANSING	2970
1645	1800	Shale & Lime	CHERTY CONG.	3235
1800	2915	Lime & Shale	SIMPSON	3308
2915	3185	Lime	ARBUCKLE	3331
3185	3210	Lime		
3210	3260	Lime & Conglomerate	ELEVATION	1781 K.B.
3260	3320	Lime & Shale		
3320	3331	Shale		
3331	3336	Dolomite		
	3336	<u>Rotary Total Depth - D & A</u>		

Set 980' of 8 5/8" surface casing with 450 sacks cement & 5 sacks CaCl.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Cress #1, located NW $\frac{1}{4}$ NE $\frac{1}{4}$ SE $\frac{1}{4}$ of Section 12, Township 11 South, Range 17 West, Ellis County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

By: Frank Hamlin
Frank Hamlin

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 26th day of November 1957.

Ruth N. Benjamin
Ruth N. Benjamin, Notary Public

My Commission Expires:
June 17, 1961.

STATE OF KANSAS
11/27/1957
NOV 27 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 12 T. 11 R. 17W
BOOK PAGE 63 LINE 31