

302 S. Clay, Liberal, KS
 217 S. Alliance Ct, Oklahoma City, OK
 5621 B Sooner Trend Rd., Enid, OK

(620) 624-4941
 (405) 495-0101
 (580) 233-8994



No 56375

Date 12-17, 2004
 Purchaser: PRISCO WESTERN
 Mailing Address: 1775 STEELMAN ST, DENVER CO, 80203-423
 State KANSAS County MASKEL Sec. 8 Twp. 28S Range 33W
 Lease: COX Field _____ Well No. 1-8

In Accordance with the terms and conditions specified on the reverse side hereof, which we hereby approve and accept, furnish the use and service of your men, material and equipment necessary to perform the services outlined below to the above well, under our direction and supervision.

Open hole insurance protection authorization —
 By Rodney Loyale Purchaser PRISCO WESTERN
 By Rodney Loyale

CASED HOLE SERVICES

OPEN HOLE SERVICES

LOGGING
 Casing Tubing
 Primary
 Pole Trk. (Specify) _____
 Computer/Laser log
 Log Distribution _____

PERFORATION
 Pressure eqmt. req'd (specify) _____
 Max. Pressure encountered _____
 No. of runs under pressure _____
 Select Fire Casing Gun
 Tubing Gun Type Chg. 3 1/2 HX
45PF

OPEN HOLE SERVICES
 Open Hole Logs
 Computer Logs
 Telecopier # _____ prints

		NET PRICE
<i>SERVICES CHANGE</i>		<u>500.00</u>
<u>Run 1)</u>	<u>SET 4 1/2 CIRP AT 3200</u>	<u>DEPTA charge X25 800.00</u>
<u>Run 2)</u>	<u>TRAF 3 1/2 HX SQUARE HOLES AT 3000 - 01</u> <u>45PF P. 1255 10 HOURS</u>	<u>900.00</u>
<u>Run 3)</u>	<u>SET 4 1/2 CEMENT RETURN AT 2925</u>	<u>DEPTA charge min X25 750.00</u> <u>LOW SET charge 175.00</u>
RECEIVED		
FEB 11 2005		
KCC WICHITA		
<u>Book Price only</u>		<u>3425.00</u>

FIELD ESTIMATE ONLY **TOTAL CHARGES**

Charges subject to correction by our Invoicing Dept. in accordance with latest price schedules

Southern Office Supply, Inc. Form 34151

Purchaser PRISCO WESTERN
 By _____
 Old New Well
 Tubing Size _____ Time Arriving 8:00 A M
 Casing Size 4 1/2 Time of Leaving 10:00 M
 Truck # 681
 Miles R. T. 100 Engineer & Crew JC SATT



TREATMENT REPORT

Customer ID		Date	
Customer PRISCO WESTERN LLC		12-18-04	
Lease COX	Lease No. 1-8	Well #	
Field Order # 9277	Station L1352AL KS	Casing 4 1/2	Depth 2925'
County HASKELL		State KS	

Type Job **SQUEEZE/RAISE CRT** Formation _____ Legal Description **8-285-33W**

PIPE DATA		PERFORATING DATA		FLUID USED		TREATMENT RESUME		
Casing Size 4 1/2	Tubing Size 2 3/8	Shots/Ft 12.2 #/ft	2.12 cuft	Acid 410 SK ASBEN LITE		RATE	PRESS	ISIP
Depth	Depth	From 1500'	To 1.34 cuft	Pre Pad 150 SK 'A'	Max			5 Min.
Volume	Volume	From	To	Pad	Min			10 Min.
Max Press	Max Press	From	To	Frac	Avg			15 Min.
Well Connection	Annulus Vol.	From	To	Flush	HHP Used			Annulus Pressure
Plug Depth	Packer Depth 2925'	From	To		Gas Volume			Total Load

Customer Representative **RODNEY GONZALES** Station Manager **JERRY BENNETT** Treater **DICK MOORE**

Service Units	28	44	70	38	75	112			
---------------	-----------	-----------	-----------	-----------	-----------	------------	--	--	--

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
0830					ON LOCATION
946	0		0		LOAD ANNULUS
947	700		1		LOADED
948		0	0		ESTABLISH INJECTION RATE
952		800	10	2.2	RATE ESTABLISHED - SHUT DOWN
1002	500	800	0	2	START CEMENT (410SK ASBEN LITE)
1007	400	300	12	2.2	CEMENT ON BOTTOM
1047	400	1150	185	2	SWITCH TO TAIL CEMENT (150 SK CLASS A)
1157	400	1200	225	2	CEMENT MIXED - SHUT DOWN - WASH UP
1208	400	1100	0	2	START DISPLACEMENT
1208	400	1100	1	2	CAUGHT CEMENT
1211	400	1700	11	1.8	SHUT DOWN
	400	1100			STRING OUT OF RESTRICTOR
1218	400	400	0	2	REVERSE OUT ↓ ANN ↑ TRNG
1226		400	20	2	SHUT DOWN - JOB COMPLETE

RECEIVED
 FEB 11 2005
 KCC WICHITA

THANK YOU FOR CALLING
 Acid Services
 DICK / SHAWN / CHAD / TONY / MANSFIELD

ALLIED CEMENTING CO., INC.

19686

Federal Tax I.D.

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Oakley

DATE 12-22-04	SEC 8	TWP 28S	RANGE 33W	CALLED OUT	ON LOCATION 9:00 AM	JOB START 9:45 AM	JOB FINISH 12:30 PM
LEASE COX				WELL # 1-8	LOCATION Sublett 10N 4W 1/4N W/5	COUNTY Haskell	STATE KS

OLD OR NEW (Circle one)

CONTRACTOR ELDredge well service OWNER same
TYPE OF JOB Squeez
HOLE SIZE _____ T.D. _____
CASING SIZE 4 1/2 DEPTH _____
TUBING SIZE 2 7/8 DEPTH 2438
DRILL PIPE _____ DEPTH _____
TOOL _____ DEPTH _____
PRES. MAX _____ MINIMUM _____
MEAS. LINE _____ SHOE JOINT _____
CEMENT LEFT IN CSG. _____
PERFS. 2676, 2698-2716, 2760'
DISPLACEMENT _____

CEMENT AMOUNT ORDERED 200SKS Com

COMMON	<u>200 SKS</u>	@ <u>9.10</u>	<u>1820.00</u>
POZMIX		@	
GEL		@	
CHLORIDE	<u>3SKS</u>	@ <u>33.00</u>	<u>99.00</u>
ASC		@	
		@	
		@	
		@	
		@	
		@	
		@	
HANDLING	<u>203 SKS</u>	@ <u>1.35</u>	<u>274.05</u>
MILEAGE	<u>54 1/2 sk/mile</u>		<u>558.25</u>
			TOTAL 2751.30

EQUIPMENT

PUMP TRUCK CEMENTER Dean
383-281 HELPER Andrew/Max
BULK TRUCK
386 DRIVER Alan
BULK TRUCK
_____ DRIVER _____

REMARKS:

Press B side 500#. Took ins ROK
4 1/2 BPM at 800#. mix 100SKS w/ 5 1/2
cc followed w/ 100SKS Com. Wash line
↓ Pump. Staged 1 1/2 hrs max pressure
1000#. reverse tub clean. Pulled
4 Joints pressure to 500# shut in

Thank you

SERVICE

DEPTH OF JOB			
PUMP TRUCK CHARGE			<u>1180.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>55 miles</u>	@ <u>4.00</u>	<u>220.00</u>
MANIFOLD		@	
		@	
		@	

RECEIVED

FEB 11 2005

TOTAL 1400.00

KCC WICHITA

PLUG & FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 D.

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Radney Gonzalez

Radney Gonzalez
PRINTED NAME