

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

Operator: License # 32640
 Name: R.E. Blaik, Inc.
 Address: PO Box 1375
 City/State/Zip: Oklahoma City, OK 73101
 Purchaser: _____
 Operator Contact Person: Bob Blaik
 Phone: (405) 236-4400
 Contractor: Name: Duke Drilling Co., Inc.
 License: 5929
 Wellsite Geologist: Mike Smith
 Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)
 If Workover/Re-entry: Old Well Info as follows:
 Operator: _____
 Well Name: _____
 Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr/SWD
 Plug Back _____ Plug Back To _____ Depth
 Conmingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____
 03-27-01 04-12-01
 Spud Date or Date Reached TD Completion Date or
 Recompletion Date Recompletion Date

RECEIVED
 KANSAS CORPORATION COMMISSION
 JUN 29 2001

API No. 15 - 025-21224-0000
 County: Clark County, Kansas
NE NE Sec. 4 Twp. 32 S. R. 22 East West
660 feet from S / N (circle one) Line of Section
660 feet from E / W (circle one) Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 (circle one) NE SE NW SW
 Lease Name: Comstock Well #: 1-4
 Field Name: Wildcat
 Producing Formation: _____
 Elevation: Ground: 2199' Kelly Bushing: 2210'
 Total Depth: 6755 Plug Back Total Depth: _____
 Amount of Surface Pipe Set and Cemented at 812 Feet
 Multiple Stage Cementing Collar Used? Yes No
 If yes, show depth set _____ Feet
 If Alternate II completion, cement circulated from _____
 feet depth to _____ w/ _____ sx cml.
 Drilling Fluid Management Plan Part A KGR1-11-08
 (Data must be collected from the Reserve Pit)
 Chloride content 2000 ppm Fluid volume 8000 bbls
 Dewatering method used evaporation
 Location of fluid disposal if hauled offsite: _____
 Operator Name: _____
 Lease Name: _____ License No.: _____
 Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
 County: _____ Docket No.: _____

CONSERVATION DIVISION

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Robert E. Blaik
 Title: President Date: 6-26-01
 Subscribed and sworn to before me this 26th day of June
 Notary Public: Norma Nell Clark
 Date Commission Expires: 6/30/2004

KCC Office Use ONLY

Letter of Confidentiality Attached
 If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

Operator Name: R.E. Blaik, Inc. Lease Name: Comstock Well # 1-4
 Sec. 4 Twp. 32 S. R. 22 East West County: Clark County, Kansas

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No
 (Submit Copy)

List All E. Logs Run:

AI/FDC-CNL

Log Formation (Top), Depth and Datum Sample

Name	Top	Datum
Stone Coral	1217	2211
Heebner	4337	"
Lansing	4532	"
Marmaton	5040	"
Pawnee	5127	"
Mississippi	5292	"
Viola	6295	"
Arbuckle	6727	"

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacs Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	24#	812'	65/35 Class A	265 150	6%gel 3%cc 3%cc 2%gel

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	# Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				


Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth

TUBING RECORD	Size	Set At	Packer At	Liner Run <input type="checkbox"/> Yes <input type="checkbox"/> No

Date of First, Resumed Production, SWD or Enhr. _____ Producing Method Flowing Pumping Gas Lift Other (Explain) _____

Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity

Disposition of Gas Vented Sold Used on Lease (If vented, Sumit ACO-18.) Open Hole Perf. Dually Comp. Commingled Other (Specify) _____



ALLIED CEMENTING CO., INC.

P.O. BOX 31
- RUSSELL, KS 67605
PH (785) 483-3887
FAX (785) 483-5566

.....
* INVOICE *
.....

Invoice Number: 083941

Invoice Date: 04/13/01

Sold R. E. Blaik, Inc.
To: P. O. Box 1375
Oklahoma City, OK
73101

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 02 2003

CONSERVATION DIVISION
WICHITA, KS

Cust I.D.: Blai
P.O. Number...: Comstock 1-4 ✓
P.O. Date.....: 04/13/01

Due Date.: 05/13/01
Terms: Net 30

Item I.D./Desc.	Qty	Used	Unit	Price	Net	TX
Common	99.00		SKS	6.3500	628.65	E
Pozmix	56.00		SKS	3.2500	214.50	E
Gel	9.00		SKS	9.5000	85.50	E
Handling	174.00		SKS	1.0500	182.70	E
Mileage (65)	65.00		MILE	6.9600	452.40	E
174 sks @\$.04 per sk per mi						
Rotary Plug	1.00		JOB	1562.0000	1562.00	E
Mileage pmp trk	65.00		MILE	3.0000	195.00	E

All Prices Are Net, Payable 30 Days Following
Date of Invoice. 1 1/2% Charged Thereafter.
If Account CURRENT take Discount of \$ 332.08
ONLY if paid within 30 days from Invoice Date

Subtotal: 3320.75
Tax: 0.00
Payments: 0.00
Total: 3320.75

PAID
MAY 14 2001
9301 *2988.67

ALLIED CEMENTING CO., INC.

P.O. BOX 31
RUSSELL, KS 67665
PH (785) 483-3887
FAX (785) 483-5566

INVOICE

Invoice Number: 083775

Invoice Date: 03/28/01

Sold R. E. Blaik, Inc.
To: P. O. Box 1375
Oklahoma City, OK
73101

Cust I.D.: Blai
P.O. Number...: Comstock 1-4
P.O. Date.....: 03/28/01

Due Date.: 04/27/01
Terms..... Net 30

Item	Qty	Unit	Price	Total	Ext
Common	150.00	SKS	6.3500	952.50	E
Lite	265.00	SKS	6.0000	1590.00	E
Gel	3.00	SKS	9.5000	28.50	E
Chloride	14.00	SKS	28.0000	392.00	E
FloSeal	66.00	LBS	1.4000	92.40	E
Handling	446.00	SKS	1.0500	468.30	E
Mileage (65)	65.00	MILE	17.8400	1159.60	E
446 sks @ \$.04 per sk per mi					
Surface	1.00	JOB	470.0000	470.00	E
Mileage pmp trk	65.00	MILE	3.0000	195.00	E
Extra Footage	512.00	PER	0.4300	220.16	E
TRP	1.00	EACH	90.0000	90.00	E
Basket	1.00	EACH	180.0000	180.00	E
Baffle Plate	1.00	EACH	45.0000	45.00	E

All Prices Are Net, Payable 30 Days Following
Date of Invoice. 1 1/2% Charged Thereafter.
If Account CURRENT take Discount of \$ 588.25
ONLY if paid within 30 days from Invoice Date

Subtotal: 5883.46
Tax..... 0.00
Payments: 0.00
Total.... 5883.46

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 02 2003

CONSERVATION DIVISION
WICHITA, KS

PAID
APR 25 2001

9266 5295.11

ALLIED CEMENTING CO., INC.

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: MECHADGE

DATE <u>3-28-01</u>	SEC <u>4</u>	TWP <u>32S</u>	RANGE <u>22W</u>	CALLED OUT <u>4:00 A.M.</u>	ON LOCATION <u>8:00AM</u>	JOB START <u>13:45</u>	JOB FINISH <u>1:30</u>
LEASE <u>Comstock</u>		WELL # <u>1-4</u>	LOCATION <u>Ashland Road Welding Shop</u>		COUNTY <u>Clark</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)		S <u>2</u> N <u>2</u> E to <u>Front House</u>		N <u>7</u> E to <u>Loc</u>			

CONTRACTOR Duke #5

TYPE OF JOB SURFACE PIPE

HOLE SIZE 12 1/4 T.D. 816

CASING SIZE 8 3/8 # 24 DEPTH 812

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT 42.13

CEMENT LEFT IN CSG. 42

PERFS. _____

DISPLACEMENT 49 bbls

EQUIPMENT _____

PUMP TRUCK CEMENTER Larry Storm

35A-265 HELPER Mike Rucker

BULK TRUCK _____

353- DRIVER Jason T.

BULK TRUCK _____

35R DRIVER Scott J.

OWNER R.E. Blaik

CEMENT

AMOUNT ORDERED 265 xks 65 35 16 + 3%

CAU-2 + 3" Flo-Seal 150 xks A +

32 CAU-2 + 2" Gel

COMMON <u>150 xks A</u>	@ <u>6.35</u>	<u>952.50</u>
POZMIX <u>265 xks</u>	@ <u>6.00</u>	<u>1590.00</u>
GEL <u>3</u>	@ <u>9.50</u>	<u>28.50</u>
CHLORIDE <u>14 xks</u>	@ <u>28.00</u>	<u>392.00</u>
<u>Flo-Seal 66 #</u>	@ <u>1.40</u>	<u>92.40</u>
	@	
	@	
	@	
HANDLING <u>446</u>	@	<u>468.30</u>
MILEAGE <u>446 x .04 x 65</u>		<u>1159.40</u>
		TOTAL <u>4683.30</u>

REMARKS:

Broke Circulation Pottery Mud
Switched Pumped 5 bbls Freshwater
Mixed 265 xks Lita to Plan 150 xks
A + 3 + 2 Displaced Plus with 49 bbls
Freshwater Plan 194 350 # Bump
Plug to 800 # Shut Plug No.
Circulation good Returns 25 bbls of
Slurry

SERVICE

DEPTH OF JOB <u>812'</u>		
PUMP TRUCK CHARGE		<u>470.00</u>
EXTRA FOOTAGE <u>512'</u>	@ <u>43</u>	<u>220.16</u>
MILEAGE <u>65</u>	@ <u>3.00</u>	<u>195.00</u>
PLUG <u>1-838TRP</u>	@ <u>90.00</u>	<u>90.00</u>
	@	
	@	
		TOTAL <u>975.16</u>

CHARGE TO: R.E. Blaik

STREET _____

CITY _____ STATE RECEIVED

KANSAS CORPORATION COMMISSION

FLOAT EQUIPMENT

<u>Basket</u>	@ <u>180.00</u>	<u>180.00</u>
<u>Baffle Part</u>	@ <u>45.00</u>	<u>45.00</u>
	@	
	@	
		TOTAL <u>225.00</u>

JAN 02 2003

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

TAX _____

TOTAL CHARGE 5883.46

DISCOUNT 5295.11 IF PAID IN 30 DAYS

Jon Livingston

PRINTED NAME