

RECEIVED
JUL 01 2005
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Form ACO-1
September 1999
Form Must Be Typed

ORIGINAL

Operator: License # 32119
Name: Northern Natural Gas Co.
Address: 1111 South 103rd Street
City/State/Zip: Omaha, NE 68013
Purchaser: _____
Operator Contact Person: Duane Moody
Phone: (402) 398-7843
Contractor: Name: McLean's C P Installation, Inc.
License: 32775

Wellsite Geologist: _____
Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl. Cathodic etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____
5-19-05 5-23-05
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date


API No. 15 - 15-175-21983-0000
County: Seward
SE SE SE Sec. 27 Twp. 31S S. R. 32W East West
496' feet from S N (circle one) Line of Section
60' feet from E W (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Valve Well #: #2
Field Name: Valve Well #2
Producing Formation: _____
Elevation: Ground: _____ Kelly Bushing: _____
Total Depth: 175' Plug Back Total Depth: _____
Amount of Surface Pipe Set and Cemented at 20' Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ ^{sq cmt.}

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content _____ ppm Fluid volume _____ bbls
Dewatering method used _____
Location of fluid disposal if hauled offsite: _____
Operator Name: Nichols Fluid Service
Lease Name: Johnson #3 License No.: 31983
Quarter _____ Sec. 16 Twp. 34 S. R. 32 East West
County: Seward Docket No.: _____

Alt 3-Dlg-2/24/09

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.
Signature: [Signature]
Title: Operations Mgr. Date: 6-23-05
Subscribed and sworn to before me this 23rd day of June
2005
Notary Public: [Signature]
Date Commission Expires: 8-31-2008



KCC Office Use ONLY
 Letter of Confidentiality Received
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

NICHOLS FLUID SERVICE INC.
316 INDUSTRIAL PARK AVE
LIBERAL, KS 67901
(620)624-5582
(620)624-4900 (fax)

ORIGINAL INVOICE

RECEIVED

JUL 01 2005

KCC WICHITA

INVOICE NO.: 150364
INVOICE DATE: 05/26/2005

VALVE 1 & 2
Seward Co KS

MCLEAN'S C. P. INST
4520 ST HWY 136
AMARILLO, TX 79108

Qty	UM	Description
TICKET # 32327 - 05/21/2005		
8.50	HR	Haul Water
60	BBL	Disposal Fee
		FSC
TOTAL FOR TICKET # 32327		
TICKET # 28826 - 05/22/2005		
5.50	HR	Haul Water
		FSC
TOTAL FOR TICKET # 28826		
TICKET # 28827 - 05/22/2005		
5.50	HR	Haul FW
120.00	BBL	Fresh Water
		FSC
TOTAL FOR TICKET # 28827		

PLEASE PAY THIS AMOUNT 

ORIGINAL

VALVE-111) NNE
Plains Ready Mix

29341

D.W. Green, Inc.
P.O. BOX 638

"ALL TYPES CONCRETE WORK"

PLAINS, KANSAS 67869

PHONE: 620-563-9382

ORDER NO. _____

DATE 5/20/05

SOLD TO McLean's LP Installation

ADDRESS _____

DELIVER TO Rd 6 2 1/2 mi north

CASH	CHARGE	TRUCK	DRIVER	Time OUT
	X			T

QUANTITY	DESCRIPTION
1 3/4	CUBIC YARDS CONCRETE Slurry
	% CALCIUM CHLORIDE
	WATER REDUCER 34 bags
	OZ. AIR ENTRAINING 5.2 0.7 lb
	HOT WATER
	FIBER
	ROCK
13 1/2	MILEAGE @ 3.00 PER CUBIC YD MILE HAUL
	HOURS WAITING TIME
	GALLONS WATER ADDED ON JOB
	SERVICE CHARGE - FOR UNDER 3 YARDS

RECEIVED
JUL 01 2005
KCC WICHITA

IMPORTANT

Not responsible for any damage done by truck after leaving street right of way. NO CREDIT for returned concrete. Unloading time allowed (1) hour.

RECEIPT AND RELEASE

This concrete designed in accordance to A.C.I. Standards. Any water added to this design will be at purchaser's risk. RECEIVED THE ABOVE MATERIAL IN GOOD CONDITION.

Sign Here _____

A SERVICE CHARGE of 2% per month, with an effective annualized rate invoice amounts if not paid by the end of the month following the month on minimum SERVICE CHARGE shall be \$1.00 per month.

Deep Well GroundBed Data:		Date: 05/21/05
Job Number: NNG53-2005KS	Drilling Contractor: McLean's CP Installation, Inc.	
Company Name: Northern Natural Gas	Facility/Line: Valve 1	Well #2
Subject: Deep Well #2	State: Kansas	
Well Depth: 175'	County: Seward	
Diameter: 10"	Other: JC	
Casing: 20'		
Type of Backfill: SC2	TEST VOLTAGE: 12.0	
Anode Type: (1) set of (12) 4"X80		

Remarks:

Depth:	Formation Type:	Material:	Electrical Log			Anode Log		
			Volt	Anode Depth	Anode #	Volt	Anode Depth	Anode #
0'	Top Soil							
5'	"	Casing						
10'	Sandy Clay	Casing						
15'	"	Casing						
20'	"	Casing/Hole Plug	2.0					
25'	"	Hole Plug						
30'	"	SC2	1.8					
35'	"	SC2						
40'	"	SC2	1.4					
45'	"	SC2						
50'	"	SC2	1.2					
55'	"	SC2						
60'	"	SC2	1.3	60'	12			
65'	"	SC2						
70'	"	SC2	1.1	70'	11			
75'	Sandstone	SC2						
80'	"	SC2	0.4	80'	10			
85'	"	SC2						
90'	Sandy Clay	SC2	1.3	90'	9			
95'	"	SC2						
100'	"	SC2	1.3	100'	8			
105'	"	SC2						
110'	"	SC2	1.0	110'	7			
115'	"	SC2						
120'	Sandstone	SC2	0.7	120'	5			
125'	"	SC2						
130'	Sandy Clay	SC2	0.9	130'	4			
135'	"	SC2						
140'	"	SC2	2.1	140'	3			
145'	"	SC2						
150'	"	SC2	1.5	150'	2			
155'	"	SC2						
160'	"	SC2	1.1	160'	1			
165'	"	SC2						
170'	"	SC2	0.5					
175'	Sandstone	SC2						
180'								
185'								
190'								
195'								
200'								
205'								
210'								
215'								
220'								
225'								
230'								
235'								
240'								
245'								
250'								

RECEIVED
JUL 01 2005
KCC WICHITA

Deep Well: Valve #1 Well #2

McLean's CP Installation, Inc.
4520 State Highway 136
Amarillo, Tx 79018

RE: WASTE DISPOSAL - FLUID MUD/CUTTINGS

Location of waste disposal:

Operator Name: Nichols Fluid Service

Date of Waste Disposal: 5-21-2005

Lease Name: Johson #3

License Number: 31983

Section: 16 Twp: 34 R 32 ~~East~~ West

County: Seward

The undersigned hereby certifier that all information shown hereon is true and correct to the best of their knowledge and belief.

Nichols Fluid Service Inc
Company Name

Danny W. Slater
Authorized Signature

Date: 5-23-2005

RECEIVED
JUL 01 2005
KCC WICHITA