

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Pauley Oil

Address: P.O. Box 163 Holyrood, Kansas 67450-0163

Phone: (785) 252-8024 Operator License #: 31327

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)
by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-159-30052-00-00

Lease Name: Rick

Well Number: 3

Spot Location (QQQQ): _____ - NE - SE - SE
9901040 Feet from North / South Section Line
330399 Feet from East / West Section Line

Sec. 17 Twp. 20 S. R. 10 East West

County: Rice

Date Well Completed: 1965

Plugging Commenced: 2-3-09

Plugging Completed: 2-7-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	197'	None
				5-1/2"	3375'	1800'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 3350' and 5 sxs. cement. Lost casing cutter down hole, Log-Tech of Ks. shot casing loose @1800'. pulled up to 1300', pumped 35 sxs/ cement, pulled casing up to next plug, couldn't pump cement, casing was plugged up. Layed 5-12" casing down, ran in 1300' of tubing, pumped 35 sxs. cement, pulled up to 950', pumped 35 sxs. cement, pulled up to 250' and circulated 100 sxs. cement. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P. O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Pauley Oil

State of Kansas County, Rice, ss.


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 10th day of February, 2009

Irene Herzberg My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 11 2009
CONSERVATION DIVISION
WICHITA, KS