

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

**Locate well correctly on above
Section Plat**

Ellis County, Sec. 18 Twp. 11S Rge. 20 (B) (W)
 Location as "NE/CNW¼SW¼" or footage from lines NW NW NW
 Lease Owner PEEL-HARDMAN
 Lease Name Walz "A" Well No. 1
 Office Address P. O. Box 359 Hoisington, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed Dec. 29 19 50
 Application for plugging filed Dec. 29 19 50
 Application for plugging approved Dec. 29 19 50
 Plugging commenced Dec. 29 19 50
 Plugging completed Dec. 29 19 50
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production.....19.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?.....Yes.....

Name of Conservation Agent who supervised plugging of this well..... C. D. Stough,..... Great Bend, Kansas.....
Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... Feet.....
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

3792' - 169 $\frac{1}{2}$ ' - Heavy Rotary Mud
169 $\frac{1}{2}$ ' - 168' - Wooden Plug
168' - 122' - 15 Sacks Cement
122' - 41 $\frac{1}{2}$ ' - Heavy Rotary Mud
41 $\frac{1}{2}$ ' - 40' - Wooden Plug
40' - 6' - 10 Sacks Cement
6' - Surface - Cellar

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to..... Peel-Hardman
Address..... P. O. Box 359, Hoisington, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Glenn Peel Drilling Company, Inc. (employee of owner) or ~~owner or operator~~ of the above-described well,
 being first duly sworn, on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
 described well as filed and that the same are true and correct. So help me God. GLENN PEEL DRILLING, INC.

(Signature).....BY:.....

PL. O. BOX 359 HOISINGTON, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of January, 1951

My commission expires June 4, 1951

22-5133-s 9-48-10M

.....
Notary Public.

PLUGGING
FILE SEC. 19 T 11 R YOW
BOOK PAGE 53 LINE 4

15-051-00669-00-00

DRILLER'S LOG

Company: Peel-Hardman

NW NW NW

Sec. 18 Twp. 11S Rge. 20W

Farm: Walz "A" Well No. 1

Comm: 12-19-50 Comp: 12-29-50

County: Ellis,
Kansas

Contractor: Glenn Peel Drilling Co., Inc.

Total Depth: 3792'

Elevation:

Casing:

8 5/8" 170' cem.

Production: Dry

Figures below indicate bottom of formations

Surface Soil	0 -	10
Post Rock		35
Clay		75
Sand, Shale & Shells		170
Shale		695
Sand		765
Sand, Shale & Shells		1486
Shale		1580
Anhydrite		1620
Shale		1755
Shale & Shells		2495
Lime & Shale		2520
Lime		2618
Shale		2635
Lime		2750
Lime & Shale		3310
Lime		3700
Shale, Lime & Chert		3724
Conglomerate & Shale		3785
Conglomerate & Chert		3792
Total Depth		3792

This is to certify that the above information is, to the best of our knowledge true and correct.

GLENN PEEL DRILLING COMPANY, INC.

BY: Wm Herbert

SUBSCRIBED AND SWORN to before me this 12th day of January, 1951.

My commission expires June 4, 1951

Marion M. Herbert
Notary Public

PLUGGING

FILE SEC. 18 T. 11S R. 20W

Wm 52 4

RECEIVED
JAN 15 1951
CONTRACT
Wichita, Kan.