

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-051-01191-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

ELLIS

County. Sec. 18 Twp. 11S Rge. (E) 20 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SW SW SW

Lease Owner. KAISER-FRANCIS

Lease Name. HANEKE Well No. 1

Office Address. 719 Union Center, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 4-25-58 19

Application for plugging filed 4-25-58 19

Application for plugging approved 4-25-58 19

Plugging commenced 4-25-58 19


Plugging completed 4-25-58 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3825' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	280'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 550' set solid plug with 20 sx cement thru drill pipe. Filled with heavy mud to 270' set solid plug with 15 sx cement thru drill pipe. Filled with heavy mud to 40' set solid bridge with 10 sx to base of cellar. Job Complete 4-25-58.

RECEIVED  
STATE CORPORATION COMMISSION  
5-2-1958  
MAY 2 1958  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor. K & E DRILLING, INC.

Address. 719 Union Center, Wichita 2, Kansas

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

Herman George Kaiser (employee or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Herman George Kaiser  
905 Palace Building, Tulsa, Oklahoma  
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of April, 1958

My commission expires June 29, 1960

Frances R. Hitchens Notary Public.

PLUGGING  
W.L. SEC 18 T. 11 S. R. 20 W  
BOOK PAGE 90 LINE 3

15-051-01191-00-00

DRILLER'S LOG

OPERATOR:	KAISER-FRANCIS 905 Palace Building Tulsa, Oklahoma	LOCATION:	#1 HANEKE SW SW SW Sec. 18-11S-20W ELLIS COUNTY, KANSAS
CONTRACTOR:	K & E DRILLING, INC. 719 Union Center Wichita 2, Kansas	CASING:	8-5/8" @ 280' (125 sx)
COMMENCED:	4-18-58	ELEVATION:	2175' KB 2172' DF
COMPLETED:	4-25-58		
R.T.D.	3825'	PRODUCTION:	D & A

FORMATION RECORD

Surface Soil	20
Rock & Shale	40
Shale	670
Sand & Shale	1060
Sand	1290
Redbed	1594
Anhydrite	1670
Shale & Shells	1685
Shale & Lime	2030
Lime & Shale	3010
Lime	3265
Lime & Shale	3360
Lime	3797
Shale	3811
Arbuckle Lime	3825
R.T.D.	3825


CERTIFICATION

STATE OF KANSAS )  
 ) SS:  
 COUNTY OF SEDGWICK )

I, Dale Silcott, of K & E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the Kaiser-Francis #1 Haneke.

  
 Dale Silcott

Subscribed and sworn to before me this 29th day of April, 1958.

  
 Patricia M. Edwards, Notary Public

My commission expires: 11 August 1958.



PLUGGING  
 TWP. SEC. 18 T. 11 R. 20 W.  
 PAGE 98 LINE 3

5-2-1958