


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-051-00351-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 18 Twp. 11S Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE NE

Lease Owner Burch Drilling Co., Inc. BOA

Lease Name Hannake Well No. 1

Office Address 1011 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-11-59 19

Application for plugging filed 3-11-59 19

Application for plugging approved 3-11-59 19

Plugging commenced 3-11-59 19

Plugging completed 3-11-59 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug set @ 600' with 20 sacks cement
2nd plug set @ 185' with 15 sacks cement
3rd plug set @ 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
4-9-1959
APR 9 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Burch Drilling Co., Inc.
Address 1011 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Earl M. Burch, President (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl M. Burch
Earl M. Burch, President

SUBSCRIBED AND SWORN to before me this 8th day of April, 1959.
My commission expires July 27, 1960.
Ginny Harrison Notary Public.



PLUGGING
FILE SEC. 18 T. 11 R. 20W
BOOK PAGE 23 LINE 33

15-051-00351-00-00

WELL LOG

Burch Drilling Co., Inc. + BOA
1 Hannake
SE SE NE, 18-11S-20W
Ellis County, Kansas

8 5/8" set @@ 238' w/150 sx.
Commenced: 3-4-59
Completed: 3-11-59
Elevation: 2121 Kelly bushing
D & A

1551 Shale & Shells
1610 Anhydrite
2040 Shale
2226 Shale & Lime streaks
2450 Shale & Lime
2580 Shale
3323 Lime & Shale
3685 Lime
3730 Cherty lime
3751 Lime


	<u>TOPS</u>	
Anhydrite		1551'
Heebner		3391
Toronto		3414
Lansing		3427
Base Kansas City		3654
Conglomerate		3693
Arbuckle		3740
Rotary Total Depth		3751

DST # 1 3476-3505 Open 1/2 hr.
Recovered 15' mud. All pressures
were zero.

DST # 2 none.

STATE OF KANSAS, COUNTY OF SEDGWICK:

I, Earl M. Burch, President of Burch Drilling Co., Inc. being
duly sworn on oath, state: That I have knowledge of the facts, statements,
and matters herein contained and that the same are true and correct.


Earl M. Burch, President

Subscribed and sworn to before me this 8th day of April, 1959.


Ginny Harrison
Notary Public

My commission expires: July 27, 1960.



RECEIVED
STATE CORP. & ASS. DIV.
4-9-1959
APR 9 1959
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 18 T. 11 R. 20W
BOOK PAGE 23 LINE 33