

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-2096-00-00

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 18 Twp. 11 Rge. 20 (E) (W) (W)

Location as "NE/CNW&SW&" or footage from lines _____
Lease Owner Beagon Resources Corporation
Lease Name W. Keller 'A' Well No. 1
Office Address 1000 Century Plaza Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-13-72 19
Application for plugging filed 1-13-72 19
Application for plugging approved 1-13-72 19
Plugging commenced 1-13-72 19
Plugging completed 1-13-72 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey Hays, Kansas 67601
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	244	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug was set @ 660' with 70 sacks cement
2nd plug was set @ 220' with 20 sacks cement
3rd plug was set @ 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
JAN 19 1972
1-19-72
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dreiling Oil, Inc.
Address Victoria, Kansas 67671

STATE OF Kansas, COUNTY OF Ellis, ss.


I, Leo F. Dreiling, Pres. of Drilg. Contrc. (and ~~employee of~~ ~~owner of~~ ~~operator of~~ ~~the~~ ~~above-described~~ well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Leo F. Dreiling

LEO F. DREILING, RT. #2 Victoria, Kans. 67671
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of January, 1972.



My commission expires September 19, 1974

JOSEPH A. HESS

Notary Public.

15-051-20796-00-00
DREILING OIL, INC.

Victoria, Kansas 67671

WELL LOG

Company **Beacon Resources**
1000 Century Plaza
Wichita, Kansas 67202

Farm **W. Keller 'A'** No. **1**

Total Depth **3,740'**

Comm. **1-4-72** Comp. **1-12-72**

Contractor **Dreiling Oil, Inc.**
Victoria, Kansas 67671

Sec. **18** Twp. **11** Rng. **20**

Location **SE NE SE**

County **Ellis**

Elevation: **2,098' K. B.**

2,095' D. F.

2,093' G. R.

Casing Record
244' = 8 5/8 "

Cement Record
100 Sacks Cement

Production:
D & A

Figures Indicate Bottom of Formations

0'	643'	Shale
643'	860'	Sand
860'	1008'	Shale
1008'	1213'	Sand
1213'	1531'	Shale
1531'	1578'	Anhydrite
1578'	2200'	Shale
2200'	2475'	Shale & Lime
2475'	2710'	Lime & Shale
2710'	2875'	Shale & Lime
2875'	3020'	Shale
3020'	3200'	Shale, Lime
3200'	3740'	Lime
3740'	T.D.	

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 19 1972
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 COUNTY OF ELLIS)

I, Leo F. Dreiling, of Dreiling Oil, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the W. Keller #1.

Leo F. Dreiling
 Leo F. Dreiling

Subscribed and sworn to before me this 14th day of January, 1972

Joseph A. Hess
 Joseph A. Hess - Notary Public

My Commission expires September 19, 1974

