


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 19 Twp. 11S Rge. 20 (E) (W)

Location as "NE/CNW/SW" or footage from lines. SE SW SE

Lease Owner Glickman Oil Co.

Lease Name Vance Well No. 1

Office Address

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed 12-31 19 68

Application for plugging filed 12-31 19 68

Application for plugging approved 12-31 19 68

Plugging commenced 7:00 AM 12-31 19 68

Plugging completed 1:00 PM 12-31 19 68

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production none 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey - Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3870 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay & Shale	0	0	208	8 5/8	208	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole - Pump 70 sx @ 720', 20 sx @ 180',
10 sx @ 40', 100 sx 6% gel. Hole plugged @ 1:00 PM
by Leo Massey & Allied Cement Co.



Name of Plugging Contractor B & B Drilling, Inc.
Address 207 Petroleum Bldg. Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lohar
207 Petroleum Bldg. Wichita Kan
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of January, 19 69

Alma A. Neiser
Notary Public.

My commission expires May 31, 1970

15-051-20377-00-00
B & B DRILLING, INC.

548 Petroleum Building
Wichita, Kansas 67202

January 3, 1969

DRILLERS LOG

Re: Vance #1
SE SW SE Sec. 19-11S-20W
Ellis County, Kansas

COMPANY: Glickman Oil Co.
CONTRACTOR: B & B Drilling, Inc.
TOTAL DEPTH: 3870'
COMMENCED: 12-17-68
COMPLETED: 12-31-68

0	94	Surface Clay
94	211	Clay & Shale
211	800	Shale
800	878	Sand & Shale
878	995	Shale
995	1125	Shale
1125	1222	Sand & Shale
1222	1368	Sand & Shale
1368	1639	Shale
1639	1686	Anhydrite
1686	2035	Shale & Lime
2035	2264	Lime & Shale
2264	2669	Lime & Shale
2269	2905	Shale & Lime
2905	3047	Lime & Shale
3047	3380	Shale & Lime
3380	3395	Lime
3395	3442	Lime
3442	3505	Lime & Shale
3505	3530	Lime
3530	3560	Lime
3560	3602	Lime
3602	3665	Lime
3665	3700	Lime
3700	3720	Lime & Shale
3720	3775	Lime
3775	3837	Lime
3837	3857	Arbuckle
3857	3870	Arbuckle
3870		Total Depth

DST #1 @ 3380

DST #2 @ 3442

DST #3 @ 3501

DST #4 @ 3536

DST #5 @ 3560

DST #6 @ 3662

DST #7 @ 3700

DST #8 @ 3820

D & A

RECEIVED
STATE CORPORATION COMMISSION
1-6-1969
JAN 6 1969
CONSERVATION DIVISION
Wichita, Kansas

We certify the above and foregoing to be true and correct copy of the log on the #1 Vance, located in Ellis County, Kansas

B & B Drilling, Inc.

Bill Baker President

Alma A. Meiser Notary Public

Subscribed and sworn to before me this
3rd day of January, 1969.

My commission expires May 31, 1970

