

15-051-23641-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ellis SEC. 20 TWP. 11 RGE. 20 W
Location as in quarters or footage from lines:
NW NE NW

Lease Owner Hellar Drilling Company, Inc.
Lease Name Denning "A" Well No. 1
Office Address 711 Petroleum Building, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed October 10, 1983
Application for plugging filed October 10, 1983
Plugging commenced October 10, 1983
Plugging completed October 10, 1983
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck
Producing formation _____ Depth to top _____ bottom _____ T.D. 3762'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

25 sx. @ 1580'

100 sx @ 800'

40 sx. @ 260'

10 sx. @ 40'

10 sx. in Rathole

Cemented with 50/50 Pozmix, 6% Gel, 3% CC

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing

STATE OF Kansas COUNTY OF Sedgwick, ss.



D.J. Iannitti (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) D.J. Iannitti
P.O. Box 308, Great Bend, KS
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of October, 19 83

Kathryn A. Voigt
Notary Public.

My Commission expires:



K. T. WOODMAN
RES. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

15-051-23641-00-00
WOODMAN & IANNITTI DRILLING COMPANY

Rotary Drilling Contractors

1022 UNION CENTER
150 N. MAIN
WICHITA, KANSAS 67202

October 14, 1983

Company: Hellar Drilling Company, Inc.
Farm: Denning "A" #1
Location: NW NE NW
Section: 20-11-20W
County: Ellis
Contractor: Woodman & Iannitti Drilling Company
Total Depth: 3762'
Comm: October 3, 1983
Comp: October 10, 1983
Casing: 8-5/8" 24# set @ 251.92' w/150 sx. Common,
3% CC, 2% Gel

Figures Indicate Bottom Formations:

251	Post Rock & Shale
283	Shale
1330	Shale
1560	Shale, Red Bed
1605	Anhydrite
1804	Shale
2160	Shale
2450	Shale
2730	Shale & Lime
2889	Shale & Lime
3035	Lime
3135	Lime & Shale
3290	Shale & Lime
3400	Lime & Shale
3510	Lime & Shale
3520	Lime & Shale
3558	Lansing
3638	Shale & Lime
3650	Shale & Lime
3715	Lime
3720	Marmation
3742	Lime & Shale
3752	Lime & Shale
3762	Lime & Shale

RECEIVED
STATE CORPORATION COMMISSION
10-19-1983
OCT 10 1983
CONSERVATION COMMISSION
Wichita, Kansas

I certify the above to be a true and correct copy of the Drillers Log to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

D. J. Iannitti
D.J. Iannitti, Partner