

15-051-00443-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis County, Sec. 20 Twp. 11 S Rge. 20 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines Center SE/4 SE/4 NW/4

Lease Owner John Lindas Oil, Inc.

Lease Name Thayer Well No. 1

Office Address 1316 Union National Bank Bldg; Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-27 19 51

Application for plugging filed 11-27 19 51

Application for plugging approved 11-27 19 51

Plugging commenced 11-27 19 51

Plugging completed 11-27 19 51

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3900 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	215'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cemented bottom plug with 155 sacks of cement at 190 feet.
Top plug with 10 sacks of cement at 40 feet.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor John Lindas Oil, Inc.

Address 1316 Union National Bank Bldg; Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Kansas

I, Edward W. Wiens (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edward W. Wiens

1316 Union National Bank Bldg. (Address)

SUBSCRIBED AND SWORN to before me this 30th day of November, 19 51

My commission expires March 25, 1952

Catherine Laroux
Notary Public.

PLUGGING
FILE SEC 20 T 11 R 203
BOOK PAGE 127 LINE 9

RECEIVED
STATE CORPORATION COMMISSION
12-1-1951
DEC - 1 1951
CONSERVATION DIVISION
Wichita, Kansas

15-051-00443-00-00

DRILLING LOG

To: The Globe Oil and Refining Company
Cities Service Oil Company
Gulf Oil Corporation

Lease: Thayer #1

County: Ellis, Kansas
Location: Center SE SE NW
Section: 20-11S-20W
Elevation: 2184' K.B. Estimated

Rotary Total Depth: 3900'
Commenced: 11-16-51; Completed: 11-27-51
Casing: 8 5/8" @ 215' with 135 sacks of cement
and 2 sacks of calcium chloride.
Cemented bottom plug with 155 sacks of cement
at 190 feet. Top plug with 10 sacks of cement
at 40 feet.

Contractor: John Lindas Oil, Inc. Rig #3
1316 Union National Bank Building
Wichita 2, Kansas

FIGURES INDICATE BOTTOM OF FORMATIONS

0	70	Surface Clay, Sand and Gravel
70	212	Shale and Shells
212	780	Shale
780	955	Sand
955	965	Shale
965	1355	Shale and Shells
1355	1635	Red Bed
1635	1675	Anhydrite
1675	1910	Shale and Shells
1910	2130	Shale and Lime
2130	2270	Shale Lime and Shells
2270	2285	Lime
2285	2475	Sand and Shale
2475	2625	Lime
2625	2965	Lime and Shale
2965	3140	Shale, Lime and Shells
3140	3235	Shale and Shells
3235	3295	Shale and Lime
3295	3785	Lime
3785	3830	Cherty Lime and Shale
3830	3841	Conglomerate and Chert
3841	3848	Simpson Sand
3848	3851	Lime and Dolomite
3851	3900	T D

PLUGGING
FILE SEC 20 T 11 R 20W
BOOK PAGE 127 LINE 9

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above statement and log is a true and correct record and log of the well drilled by John Lindas Oil, Inc. at the location above described.

Edward W. Wiers

12-1-1951

Subscribed and sworn to before me, this 30th day of November, 1951.

Catherine Roney

My commission expires March 25, 1952.