

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Indian Oil Co., Inc.

Address: PO Box 209

Phone: (620) 886-3763 Operator License #: 31938

Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 10/13/2008 (Date)

by: Steve Bond (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Cherokee Depth to Top: 4472 Bottom: 4476 T.D. 4515

Chase Group Depth to Top: 2277 Bottom: 2287 T.D. 4515

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-047-20488 -00-00

Lease Name: Jimmie

Well Number: 1-6

Spot Location (QQQQ): SW - NE - NE -

990 Feet from ☒ North / ☐ South Section Line

990 Feet from ☒ East / ☐ West Section Line

Sec. 6 Twp. 25 S. R. 17 ☐ East ☒ West

County: Edwards

Date Well Completed: 7/24/1979

Plugging Commenced: 1/20/2009

Plugging Completed: 1/22/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Cherokee	oil & gas	0	599'	8-5/8"	599'	0'
Chase Group	water	0	4515'	4-1/2"	4515'	628'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 2230' w/ 2 sx cmt on plug.

Cut casing unsuccessfully at 1752' and 1110'. Successful at 628'.

Run tbg to 690'. Pump 10 sx gel ahead of 60 sx cement.

Pull tbg to 60' and pump 100 sx cmt to surface

Name of Plugging Contractor: Eagle Well Service, DBA Bronco Energy Service

License #: 7407

Address: PO Box 1597, Liberal, KS 67905-1597


Name of Party Responsible for Plugging Fees: Indian Oil Co., Inc.

State of Kansas County, Barber, ss.

Joscelyn Nittler

(Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Joscelyn Nittler

(Address) 2507 SE US HWY 160, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 12 day of February, 20 09

Tommi J. Cox  
Notary Public

My Commission Expires: 9-26-12

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 13 2009

CONSERVATION DIVISION  
WICHITA, KS