

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior INC
Address: P.O.Box 399 Garden City, Ks 67846
Phone: (620) 275-2963 Operator License #: 4058
Type of Well: oil (OAS) KCCPT PROPER Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 2-6-2009 (Date)
by: Eric MacLaren District 1 (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Miss. Depth to Top: 5162 Bottom: 5216 T.D. 6115

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-033-21,254-00-00
Lease Name: Brass
Well Number: #1-6
Spot Location (QQQQ): C - SW - SE - NW
2060 Feet from North / South Section Line
1630 Feet from East / West Section Line
Sec. 6 Twp. 32 S. R. 18 East West
County: Comanche
Date Well Completed: 9-29-2001
Plugging Commenced: 2-10-09
Plugging Completed: 2-11-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0	618	8-5/8"	618	None
	Production	0	6030	5-1/2"	6030	2850

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 5100' dump 2 sks cement on top, Shot off 5-1/2" csg @ 2850', pull csg to 1100', pump 12 sks gel & 50 sks cement, pull csg. to 640' pump 50 sks cement, pull csg. to 260' pump 30 sks cement, pull csg. to 40' pump 10 sks cement, pull csg. out, top off wash up. Shut down, Cement 60/40 poz 4% gel, 2-11-09 top off 8-5/8" csg w/ 2-1/2 yds, Redimix, cut off casing, fill cellar.

Name of Plugging Contractor: Swift Services INC License #: 32382-33645
Address: P.O.Box 466 Ness City, Ks 67560
Name of Party Responsible for Plugging Fees: American Warrior INC
State of Kansas County, Finney, ss.

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 12 2009
CONSERVATION DIVISION
WICHITA, KS

Kevin Wiles Sr / Production Supt, (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

ERICA KÜHLMEIER
Notary Public - State of Kansas
My Appt. Expires 091209

(Signature) _____
(Address) P.O.Box 399 Garden City Ks 67846

SUBSCRIBED and SWORN TO before me this 11th day of February 2009

Notary Public My Commission Expires: 091209

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]