

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior INC
Address: P.O.Box 399 Garden City, Ks 67846
Phone: (620) 275-2963 Operator License #: 4058
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 2-2-2009 (Date)
by: Pat Staab District 4 (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
KC Depth to Top: 3100 Bottom: 3154 T.D. 3426

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-30,380-00-00
Lease Name: Besthorn
Well Number: #1
Spot Location (QQQQ): C - SW - SW - SE
330 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 23 Twp. 16 S. R. 11 East West
County: Barton
Date Well Completed: 9-19-1965
Plugging Commenced: 2-9-09
Plugging Completed: 2-10-09

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|------------|--|------|--------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| | Surface | 0 | 221 | 8-5/8" | 221 | None |
| | Production | 0 | 3423 | 5-1/2" | 3423 | None |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforate 2- holes @ 1388', 700', 360', ran tbg to 3380' pump 50 sks cement & 100#s hulls, pull tbg to 2900' pump 15 sks gel, pull tbg, to 1400' pump, 150 sks cement & 300#s hulls, pull tbg out, hook-up to 5-1/2" csg circulate 45 sks cement to surface, Shut In w/ 200#s press, wash up rig down, (Cement 60/40 poz w/ 4% gel) cut off casing. fill cellar,

Name of Plugging Contractor: Swift Services INC License #: 32382

Address: P.O.Box 466 Ness City, Ks 67560

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: American Warrior INC

FEB 12 2009

State of Kansas County, Finney, ss.

Kevin Wiles Sr / Production Supt,

(Employee of Operator) or (Operator) on above-described well, being first duty

CONSERVATION DIVISION
WICHITA KS

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]

(Address) P.O.Box 399 Garden City Ks 67846

SUBSCRIBED and SWORN TO before me this 11th day of February, 20 09

[Signature]
Notary Public

My Commission Expires: 09-12-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten Initials]