


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Trego County, Sec. 15 Twp. 11 Rge. 21 (E) W (W)

Location as "NE/CNW/SW" or footage from lines. NW NW SW
Lease Owner Don E. Pratt Oil Operations
Lease Name Anderson Well No. 1
Office Address P.O.Box# 370 Hays, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 9-17-1966
Application for plugging filed 9-17-1966
Application for plugging approved 9-17-1966
Plugging commenced 9-17-1966
Plugging completed 9-17-1966
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3844' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE PIPE				8-5/8"	153'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with rotary mud to a depth of 540' where 1st plug was set using 20 sacks cement. Filling hole with rotary mud to a depth of 180' where 2nd plug was set using 20 sax cement. Rotary mud was used to fill hole to a depth of 40' where 3rd plug was set using 10 sax cement & 1/2 sax Hulls and filling hole to surface.

RECEIVED
STATE CORPORATION COMMISSION
9-20-1966
SEP 20 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Route # 2 Victoria, Kansas

STATE OF KANSAS, COUNTY OF ELLIS, ss.

I, Leo F. Dreiling (employee of owner) or (owner/contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling

LEO F. DREILING Victoria, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of September, 19 66

My commission expires October 26, 1968

Elmer Weltz
Elmer Weltz

Notary Public.

15-195-30138-00-00

L. J. DREILING and SONS, Inc.

VICTORIA, KANSAS

WELL LOG

Company Don E. Pratt Oil Operations
Hays, Kansas

Farm Anderson No. # 1

Total Depth 3844'

Comm. 9-10-66 Comp. 9-17-66

Contractor L. J. Dreiling & Sons, Inc.
Victoria, Kansas

Sec. 15 Twp. 11 Rng. 21

Location NW-NW-SW

County Trego
2214 K.B.

Elevation: 2211 D. F.

2209' G. R.

Casing Record

Cement Record

Production:

153' 8-5/8"

125 sax HA-4

D & A

Figures Indicate Bottom of Formations

0'	153'	Top Soil-Sand & Clay
153'	678'	Shale
678'	1155'	Shale
1155'	1370'	Sand
1370'	1471'	Shale & Red Bed
1471'	1671'	Shale & Red Bed
1671'	1719'	Anhy.
1719'	1793'	Shale
1793'	2200'	Shale
2200'	2275'	Shale -Lime Strks.
2275'	2485'	Shale & Lime
2485'	2580'	Shale & Lime
2580'	2605'	Shale
2605'	2870'	Shale & Lime
2870'	2995'	Shale & Lime
2995'	3155'	Shale & Lime
3155'	3250'	Shale & Lime
3250'	3400'	Lime & Shale
3400'	3466'	Lime & Shale
3466'	3555'	Lime
3555'	3631'	Lime
3631'	3783'	Lime
3783'	3752'	Lime
3752'	3800'	Lime
3800'	3844'	Lime
3844'	R.T.D.	


RECEIVED
STATE OF KANSAS
9-20-1966
SEP 20 1966
CONSERVATION DIVISION
Topeka Kansas

STATE OF KANSAS)
)ss
COUNTY OF ELLIS 0

I, Leo F. Dreiling, of the L.J.Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Anderson # 1.

Leo F. Dreiling
LEO F. DREILING

Subscribed and sworn to before me this 19th day of September 1966.



Elmer Weltz
NOTARY PUBLIC

My commission expires: October 26, 1968