

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

15-195-21460-00-00
 WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-19521960-00-00 21460 EG 21469

LEASE NAME STRATTON

WELL NUMBER 2

3630 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 18 TWP. 11 RGE. 21 KK) or (W)

COUNTY TREGO

Date Well Completed na

Plugging Commenced na

Plugging Completed 7-20-98

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR DAVIS PETROLEUM, INC.

ADDRESS R.R. 1 BOX 183 B GREAT BEND, KANSAS 67530

PHONE(S) (316) 793-3051 OPERATORS LICENSE NO. 4656

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 20, 1998 (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? no

Producing Formation anhy Depth to Top _____ Bottom _____ T.D. 3920'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface		0	303	8 5/8"	303'	none
production		0	3918	4 1/2"	3918'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

Pump down backside W/75 sx. Cement Max 600#, Shut in 280#

PUMP DOWN 4 1/2" W/30 sx. cement W/300# hulls, follow W/12 sx. gel W/100# hulls

Follow with 100 sx. cement. Max 1200# Shut in 500#

Total 200 sx. 60/40 - 12 sx. Gel - 400# hulls

Name of Plugging Contractor Allied Cementing License No. _____

Address Russell Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Davis Petroleum, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Mike Kasselmann

(Employee of Operator) or (XXXXXXXX) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kasselmann

(Address) Mike Kasselmann
 R.R. 1 BOX 183-B GREAT BEND, KS.
 67530

SUBSCRIBED AND SWORN TO before me this 11th day of August, 19 98

Bessie M. DeWerff

Notary Public
 Bessie M. DeWerff

My Commission Expires: 5-20-2001

NOTARY PUBLIC - State of Kansas
 BESSIE M. DeWERFF
 My Appt. Exp. 5-20-2001

Form CP-1
 Revised 05-88