

15-195-22011-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-22,011-00-00

LEASE NAME Ehlenburg

WELL NUMBER 1

990 Ft. from S Section Line

3,630 Ft. from E Section Line

SEC. 22 TWP. 11 RGE. 21 ~~XX~~ Kor (W)

COUNTY Trego

Date Well Completed 4-26-89

Plugging Commenced 4-26-89

Plugging Completed 4-26-89

RECEIVED
STATE CORPORATION COMMISSION
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

JUL 24 1989
7-24-1989

CONSERVATION DIVISION
McNames & Patterson

LEASE OPERATOR McNames & Patterson

ADDRESS P.O. Box 20058, Wichita, KS. 67208

PHONE# (316) 733-5750 OPERATORS LICENSE NO. _____

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-26-89 (date)

by Gib Scheck (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3,975'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	252'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spot 20 sax cement @3,950'. Push bridge plug to 1,750', pump 20 sax cement down 4 1/2" drill pipe. Push bridge plug to 975', pump 100 sax cement down 4 1/2" drill pipe. Push bridge plug to 300', pump 40 sax cement down 4 1/2" drill pipe. Push bridge to 40', dump 10 sax cement on plug to cellar. Dump 10 sax cement down rat hole and 10 sax cement down mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co., Inc. License No. 164

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McNames & Patterson

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman (Employee of ~~SHIELDS~~) or (~~SHIELDS~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 9th day of May, 19 89


My Commission Expires: _____
RUTH PHILLIPS
State of Kansas
Notary Public
My Appt. Exp. 3-26-91



WELL LOG

Operator: McNames & Patterson
Well: Ehlenburg #1
Commenced: April 17, 1989
Completed: April 26, 1989
Contractor: Shields Drilling Co., Inc.

Well Description: NW SE SW
Sec. 22-11S-21W
Trego Co., Kansas



CASING RECORD		
Size	Run	Pulled
8 5/8"	252'	Cmtd. w/150 sax

Elevation: 2,277' KB
Treatment:
Production: D & A
Tops:

..... Figures Indicate Bottom of Formations

Clay & sand	258'	
Shale & sand	1,719'	
Anhydrite	1,770'	
Shale	2,204'	
Shale & lime	3,533'	
Lime	3,975'	RTD